

Г



THIS DRAWING IS THE PROPERTY OF MANNING ELLIOTT PARTNERSHIP. IT MUST NOT BE COPIED OR REPRODUCED OR DIVULGED TO ANYONE WITHOUT PERMISSION.

DO NOT SCALE OFF THIS DRAWING. ANY DISCREPANCIES TO BE REPORTED TO MANNING ELLIOTT PARTNERSHIP

REVISIONS: A. 2021-07-22 First issue

MANNINGELLIOTT PARTNERSHIP

Chartered Architects & Designers

Manelli House, Suite 1 Cowper Road, Penrith Cumbria CA11 9BN

t: 01768 868 800 e: post@manning-elliott.co.uk w: manning-elliott.co.uk

project title:

MOORLEYS, Egremont CA22 2UA Proposed refurbishment of farmhouse and conversion of barn

drawing title:		
Propsed site layout and		
drainage details.		
icouo stago:		

issue stage:
Construction

Construction		
date:	drawn:	scale @ A2:
July 2021	GLS	1:200
drawing number:		revision:
2102-C-200		А

Regulations 2015 and the client is to ensure that a suitable principal designer and principal contractor is appointed and must agree any transfer of duties under CDM2015 to the appointed persons who will become responsible for compliance

Health and Safety Notification procedures are to be carried out by the client or

Principal contractor is to agree the site set-up, working limits, safe access routes, material delivery and storage areas and welfare facilities with the client and describe same in his pre-construction plan and clearly identify/barrier these areas during the

Scan for, detect and record all buried services in areas of excavations before commencing work, isolate and make safe or divert any items affected by the new

The project involves extensive excavation and spoil movement which will require planning and monitoring to reduce risk to other workers and off site persons from

Ensure full support is provided to all temporary retained structural elements and seek advice from Structural Engineer if unsure of requirements.

Provide suitable equipment for lifting and placing steel beams and materials to required working height and provide safe working access and platforms for installers. Any work carried out on existing drainage to be controlled to avoid infection risk. The building construction form follows traditional methods and materials for dwellings that are anticipated as being able to be controlled and managed by a competent contractor, any concerns or unforeseen hazards to be referred to the