



Ground Control Limited

Kingfisher House
Radford Way
Billericay
Essex CM12 0EQ

T 01277 650 697

E info@ground-control.co.uk

www.ground-control.co.uk

Removal of 2 x self-seeded sycamore trees

Individually remove branches from the crowns of the two trees. The stems will then be sectionally felled. The tree rooted on the Tesco side of the palisade fence will be cut to as close as ground level as is feasible. The tree rooted on the railway side will be cut back to fence line. Eco-plugs will be inserted into the stumps to prevent regrowth.



