



**IAIN TAVENDALE F.Arbor.A.**

---

ARBORICULTURAL CONSULTANT

***Arboricultural Impact Assessment***

***Site;***

***Former Orgill Infants Schhol, Egremont.***

***Client:***

***Gleeson Homes.***

## **Tree Survey and Methodology**

A tree survey of the trees within or in close proximity to the site was prepared on the 2<sup>nd</sup> September 2020 all in accordance with BS5837:2012 Trees in Relation to Design, Demolition and Construction - Recommendations.

A detailed site topographical survey had also been prepared upon which all relevant tree survey information has been imported to produce the Tree Survey Plans – shadow and no shadow.

The survey was undertaken from ground level. No excavations were carried out or soil or root samples taken. If a more detailed assessment / inspection of any particular aspect was deemed necessary, it has been noted in the survey schedule. No aerial inspections or invasive probings or drillings have been undertaken.

Retention values were evaluated following guidance within Table 1 of BS5837 – ‘Cascade Chart for Tree Quality Assessment.’ This specifies four main categories.

1. *CAT A – Trees of high quality with an estimated remaining life expectancy of at least 40 years.* Items that could make a substantial long term contribution to the area.
2. *CAT B – Trees of moderate quality with an estimated remaining life expectancy of at least 20 years.* Specimens that are still of sufficient quality to make a substantial contribution to the area.
3. *CAT C – Trees of low quality with an estimated remaining life expectancy of at least 10 years or young trees with a stem diameter below 150mm.* All items within this category could be retained but would not be expected to impose a significant constraint on development.
4. *CAT U – Trees in such a condition that they cannot be realistically retained as living trees in the context of the current land use for longer than 10 years. They can however have existing or potential conservation value which it might be desirable to preserve.*

Management recommendations have been indicated where considered appropriate and necessary to promote tree health and viability and maintain an acceptable level of safety in respect of existing site conditions and the knowledge that development is proposed.

## **General Description of Site and Surroundings**

The site and surroundings have been indicated in detail within other plans / submissions.

In respect of arboricultural issues, trees and hedges exist predominantly to the north eastern section of the site where they have been retained in areas of previously managed open space, all of which is now neglected and in poor condition.

An inspection of the site or review of the Tree Survey Report will indicate that the two larger sycamore and single Elm tree under consideration are in comparatively poor condition and not considered to be of a quality or potential that would merit any long term retention.

The two younger sycamore have reasonable vitality but are of a size and age where it would be considered that removal and replacement planting would be acceptable.

The hedge is of minimal value and would almost certainly be lost in any site remediation exercise.

At present all trees are reasonably protected whilst the site is being utilised as a construction compound but, any future remediation / clearance works would inevitably result in the loss of all material to achieve a reasonable development.

Soils within the area and / or the site have not been analysed however, the establishment of trees within the area indicate soils are probably within the neutral to acid range and not permanently waterlogged. The size and growth rates of the general tree population also suggest that soils are relatively fertile and the local microclimates reasonably mild and / or sheltered.

### **Description of Proposed Construction**

All such issues have been fully addressed in associated submissions prepared by Gleeson Homes & Regeneration.

### **Designation Relating to Trees**

The status of the trees under consideration is not known. As such, no works should be undertaken without due notification to and consent from the Local Authority.

The potential effect of construction on trees whether statutorily protected or not is a material consideration that is taken into account in dealing with planning applications.

Although the items may be afforded statutory protection, such an order imposes no duty on the owners of the tree affected to carry out pruning or other maintenance, either to any particular standard or at all.

This must be a matter for the owners' discretion, subject to the duties laid upon him or her by the common law. If a local authority wishes to encourage such works to be carried out, it must do so by permission, through the offer of grants or possibly by the imposition of conditions on consents.

### **Current Situation**

Management of the various trees identified –appears to have been non-existent / limited in recent years with all specimens under consideration having been left untouched.

The presence of trees in locations close to 3<sup>rd</sup> party land does however generate an obligation of safety to third parties and such obligations may necessitate future management requirements should any trees be retained. It is probable however that any such works will only be implemented as and when deemed necessary.

The location of the trees to the boundary has permitted the creation of a spacious, open central environment with good sunlight penetration.

### **Implications of Development**

#### **1. Direct Loss of Trees.**

To undertake the construction of the proposed dwellings, the following trees require removal.

<b>BS5837 CAT</b>	<b>TREE No's</b>	<b>TOTAL</b>
Cat – A High Quality	None	0
Cat – B Moderate Quality	None	0
Cat – C Low Quality	T1, T2, T3, T4, T5 & H1	5 trees and 1 hedge.
Cat – U Poor Quality	None	0

*The loss of these trees will have a moderate impact upon the local environment when viewed from public areas outside the site – all of which can be mitigated by new landscape planting.*

### **Indirect Construction Impacts in General.**

As stated previously all remaining trees and hedges will be cleared from the site for development purposes.

Replanting will be implemented all as indicated on the submitted plans and such material will mitigate any losses and introduce a new and appropriate treescape to the local environment.

Construction will inevitably cause some damage and disturbance to soils and soil structure within the replanting areas.

Protection of these soils could be considered but, due to the extent of the development and inevitable access required, such options are not realistic.

It would simply be proposed therefore that all replanting areas are suitably excavated and soil improvements implemented before insertion of new stock so as to maximise viability and establishment.

*The implementation of such practices will have a positive impact on the continuation of a secure and healthy tree cover.*

### **Construction Methodology / Arboricultural Method Statement.**

Due to the loss of all remaining trees from the site, there is no requirement for any construction or arboricultural method statements to assist in the protection of retained trees.

### **Proximity of Trees to Structures.**

New trees have been positioned to allow for future growth without conflict with structures and / or light availability to dwellings and useable garden areas.

The proposed units will have good light availability, and any future concerns relating to perceived threats or shade would not be considered an issue.

Species selection would be appropriate for the individual locations and an acceptable juxtaposition achieved.

In respect of seasonal nuisances, it would not be considered that selected species or locations would create any conflicts that could result in tree loss in future years.

*In consideration of the foregoing assessments, it is considered that there will be beneficial visual impacts generated by the new plantings.*

### **Services**

The location of services into or out of the units would be expected to simply follow the road network and will therefore have no impact upon the expected root protection areas of the new plantings.

*There will therefore be neutral impact caused by the provision of services.*

## **Post Construction**

Should the dwellings be constructed, the new landscaping and tree planting will be managed as part of the overall local environment to promote visual amenity and maintain acceptable levels of safety and accessibility. Such actions will promote tree health and viability and will maximise the potential of the treescape.

*It is therefore considered that there will be no post development pressures resulting in impacts on the future potential of the local treescape.*

## **Conclusions**

From the foregoing information it can be reasonably concluded that all trees require removal for site remediation and the construction of the proposed dwellings.

The replanting proposals have considered the design and layout of the dwellings and will permit the new dwellings to exist without conflict with retained trees. The juxtaposition of the structures to trees will have no material impacts, the need for regular pruning regimes will be avoided, and seasonal nuisances minimised.


All services can be connected and / or installed without impacting upon the replacement planting.

Post construction impacts have been considered which indicate that the treescape will be positively managed resulting in the continuing health and viability of the local treescape.

*It is reasonable to conclude therefore that in respect of arboricultural issues should the proposed construction proceed there is likely to be no material impact on the future viability of the replacement treescape.*

**Iain Tavendale F.Arbor.A**

**September 2020**



**IAIN TAVENDALE F.Arbor.A.**

ARBORICULTURAL CONSULTANT

**SURVEY DETAILS FOR TREES ON LAND AT FORMER ORGILL SCHOOL, CROADALLA AVENUE,  
EGREMONT, CUMBRIA, CA22.**

**Issued to: Gleeson Homes**

**02 September 2020**

Prepared by: *Iain Tavendale F.Arbor.A*  
*High Bank Farm*  
*Stoneybank Road*  
*Earby*  
*Barnoldswick*  
*Lancs BB18 6LD*  
Phone/Fax: *01282 853333*  
*07836 246062*  
Email : *iaintavendale.co.uk*

**Note:**

All tree surgery and felling works detailed should be carried out to a standard, the minimum of which is specified in BS3998:2010 Tree Work - Recommendations.

Contractors should be suitably qualified and experienced to an acceptable standard. They should also be aware that if during operations any defects become apparent that would not have been immediately obvious to the Consultant, that such defects should be notified immediately and confirmed in writing within a reasonable period.

All observations and recommendations only relate to the site and the trees as they were at the time of inspection. Should severe climatic or environmental events or changes take place, it may be necessary to reassess the situation so as to ensure an acceptable and continuing level of safety.

Should the inspection have taken place during the dormant season, this will have simplified the inspection of the high crowns and canopies. It will not have been possible however to ascertain either leaf size, colour or density which, can be classic indicators of stress or root associated disorders.

The survey has also been prepared in the knowledge that some form of development may occur on the site. As such, some of the recommendations put forward could be considered unnecessary were the site simply left as it presently exists.

Furthermore, should development be approved, it may be necessary to reassess and amend this document upon completion of all construction operations to ensure that trees, properties and people can all safely co-exist.

All tree numbers refer to those indicated on the attached site drawing. Dimensions of any trees off site may have been estimated if access was not possible.

The report unless stated otherwise, is of a preliminary nature in that the trees were not climbed but inspected from ground level, and no soil or timber samples have been taken for analysis.

A copy of the Consultant's General Conditions of Contract are attached. These form the basis upon which all services and information are provided.



**KEY:**

**Tree No.** - Tree Number – to be recorded on tree survey plan where necessary.

**Species** – common and scientific names, where possible.

**Height** – overall height of the tree in metres

**Stem Dia** - Stem diameter – in millimetres at 1.5m above adjacent ground level (on sloping ground to be taken on the upslope side of the tree base) or immediately above the root flare for multi stemmed trees.

**Branch spread** – in metres taken at the four cardinal points to derive an accurate representation of the crown (to be recorded on the tree survey plan where necessary).

**Height of cc** - Height of crown clearance – in metres above adjacent ground level to inform on ground clearance, crown stem ratio and shading). Where considered desirable, first significant branch and direction of growth e.g. 2.4-N

**Age class** – young (Y), Middle aged (MA), mature (M), over mature (OM) & veteran (V).

**Physiological condition** – e.g. good (g), fair (f), poor (p) & dead (d).

**Structural condition** – e.g. collapsing, the presence of decay and any physical defect.

**Preliminary management recommendations** – including further investigations of suspected defects that require more detailed assessment and potential for wildlife habitat.

**ERC** - Estimated remaining contribution – in years, <10, 10+, 20+, 40+.

**Cat grade** - Category grade – U or A to C (see Table 1) to be recorded in plan on the tree survey plan where appropriate.

**RPA** – Root protection area calculated from BS5837:2012 Trees in Relation to Design, Demolition and Construction – Recommendations in sq/m's. Where indicated, dimensions of radius of circle or sides of square based around centre point of trunk calculated for design purposes.

**RP** – Remedially prune: remove significant dead wood, basal & epicormic shoots, broken, crossing and rubbing branches etc and undertake light reshaping if necessary to improve form and balance/ abate actual or potential nuisance. Ensure adequate clearances over highway (5.2m) and footpath (2.4m)

**#** - estimated dimensions (e.g. for off-site or otherwise inaccessible trees where accurate data cannot be recovered).

Table 1 Cascade chart for tree quality assessment

Category and definition	Criteria (including subcategories where appropriate)			Identification on plan
Trees unsuitable for retention (see Note)				
<b>Category U</b> Those in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years	<ul style="list-style-type: none"><li>Trees that have a serious, irremediable, structural defect, such that their early loss is expected due to collapse, including those that will become unviable after removal of other category U trees (e.g. where, for whatever reason, the loss of companion shelter cannot be mitigated by pruning)</li><li>Trees that are dead or are showing signs of significant, immediate, and irreversible overall decline</li><li>Trees infected with pathogens of significance to the health and/or safety of other trees nearby, or very low quality trees suppressing adjacent trees of better quality</li></ul> <p><i>NOTE Category U trees can have existing or potential conservation value which it might be desirable to preserve; see 4.5.7.</i></p>			See Table 2
	1 Mainly arboricultural qualities	2 Mainly landscape qualities	3 Mainly cultural values, including conservation	
Trees to be considered for retention				
<b>Category A</b> <b>Trees of high quality</b> with an estimated remaining life expectancy of at least 40 years	Trees that are particularly good examples of their species, especially if rare or unusual; or those that are essential components of groups or formal or semi-formal arboricultural features (e.g. the dominant and/or principal trees within an avenue)	Trees, groups or woodlands of particular visual importance as arboricultural and/or landscape features	Trees, groups or woodlands of significant conservation, historical, commemorative or other value (e.g. veteran trees or wood-pasture)	See Table 2
<b>Category B</b> <b>Trees of moderate quality</b> with an estimated remaining life expectancy of at least 20 years	Trees that might be included in category A, but are downgraded because of impaired condition (e.g. presence of significant though remediable defects, including unsympathetic past management and storm damage), such that they are unlikely to be suitable for retention for beyond 40 years; or trees lacking the special quality necessary to merit the category A designation	Trees present in numbers, usually growing as groups or woodlands, such that they attract a higher collective rating than they might as individuals; or trees occurring as collectives but situated so as to make little visual contribution to the wider locality	Trees with material conservation or other cultural value	See Table 2
<b>Category C</b> <b>Trees of low quality</b> with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150 mm	Unremarkable trees of very limited merit or such impaired condition that they do not qualify in higher categories	Trees present in groups or woodlands, but without this conferring on them significantly greater collective landscape value; and/or trees offering low or only temporary/transient landscape benefits	Trees with no material conservation or other cultural value	See Table 2

Tree No.	Species	H'gt.	Stem Dia.	Branch Spread	H'gt of C.C.	1st Branch @	Age Class	PC	Structural Condition	Preliminary Management Recommendations	ERC	Cat Grade	RPA Sq.m's	RPA Circle of Radii / m's
T1	Sycamore	7	375	N E S W 4.7 6.5 4.8 4	2	1.5NE	M	F/P	Approx. 50% bark loss to main trunk. Some wound tissue formation but will never achieve full compartmentalisation. 1st limb to NE damaged with incipient decay adjacent to fork. Decurrent form. Thin / sparse canopy. Small leaves. Limited potential.	Preferable to fell and implement new landscape planting.	10	C2	63.63	4.5
T2	Elm	6	300	N E S W 5 3.9 3.6 3.8	0		EM	F	Probably twin stemmed but stem to west cut back leaving badly pruned stump with incipient decay. Some random regrowth all of poor form. Remaining stem biased to east. Low vitality. Minor dead wood, old branch stumps and similar all typical of species. Susceptible to Dutch Elm Disease.	Preferable to fell and implement new landscape planting.	10	C2	40.72	3.6
T3	Sycamore	6	150	N E S W 3 1.5 2 2	2	1.5NE	Y	F	Reasonable vitality. Mutually suppressed with T4. Probably self set.	Preferable to fell and implement new landscape planting.	10	C2	10.18	1.8
T4	Sycamore	6	125	N E S W 2 1 1 1.5	2.5	3N	Y	F	Reasonable vitality. Mutually suppressed with T3. Probably self set.	Preferable to fell and implement new landscape planting.	10	C2	7.07	1.5
T5	Sycamore	12	500	N E S W 5.7 5.6 5.3 5	4		M	F	Stem bifurcates at 1.3m. Large wound with incipient decay below main fork to North. Other occluded and partially occluded pruning wounds to stem also with early decay. Reasonable form and balance.	Remove or retain in accordance with development proposals. Has limited potential and removal and replanting would be a pro-active management proposal.	10	C2	113.11	6

H1	Privet	2.5	75	N E S W	0.75	0		M	F	Reasonably well cut boundary feature.	Remove or retain in accordance with development proposals.	10	C2	2.55	0.9
----	--------	-----	----	------------------	------	---	--	---	---	---------------------------------------	--	----	----	------	-----

**IAIN TAVENDALE F.Arbor.A**  
**ARBORICULTURAL CONSULTANT**  
**General Conditions of Contract**

**1. DEFINITIONS**

In these Conditions:

"Consultant" means Iain Tavendale F.Arbor.A.

"Contract" means the contract for the provision of Services.

"Employer" means the person whose request for the provision of the Services is accepted by the Consultant or who accepts a written quotation of the Consultant.

"Site" means the area in which the Services are to be carried out as specified in writing to the Consultant prior to his commencing the provision of the Services.

"Services" means the services of arboricultural consultant to be supplied to the Employer by the Consultant in accordance with these Conditions.

**2. BASIS OF THE CONTRACT**

The consultant shall provide to the Employer and the Employer shall accept the Services in accordance with any written quotation of the Consultant which is accepted by the Employer or any request to provide services of the Employer which is accepted by the Consultant to appropriate British Standards and within a reasonable time. Time shall not be of the essence of the Contract. These conditions shall govern the Contract to the exclusion of any other terms and conditions and no variation to these Conditions shall be binding unless agreed between the Employer and the Consultant. No variation of the Services will be made without prior agreement in writing between the Employer and the Consultant. (The Consultant's employees or agents are not authorised to make any representations concerning the Services unless confirmed by the Consultant in writing.)

**3. THE CONSULTANT SHALL:**

- a) be entitled to subcontract assign or transfer any or all of the Contract without informing the Employer. The Consultant shall be responsible for its obligations under the Contract where sub-contracting takes place.
- b) be responsible for making good at his own cost any damage caused as a result solely of his own work.
- c) on completion of the Contract leave the site reasonably clean and tidy from his own work.

**4. THE EMPLOYER SHALL:**

- a) be responsible for ensuring that the Consultant is notified of all Tree Preservation or Conservation Area Orders, Private Covenants, the need for Felling Licences, or Planning Legislation that is applicable to the Contract.
- b) be responsible for ensuring that the Consultant is notified of all springs, wells, service pipes and cables, sewage or land drains, or any other hazards or obstructions which are not discoverable upon immediate visual inspection of the surface of the site. Any breach of this responsibility shall entitle the Consultant to make a reasonable charge for any additional work caused by such hazards or obstructions.

**5. CONTRACT PRICES**

The price for the Services shall not include Value Added Tax which the Employer shall be additionally liable to pay to the Consultant. The price which the Employer shall be liable to pay shall be determined by reference to the Consultants hourly charge rate current at the date of completion of the Services. In addition the Employer shall be liable to reimburse the Consultant for such expenses as may reasonably and properly be incurred by him in the performance of the services as Consultant. Written details of the Consultant's hourly charge rate will be provided to the Employer on written request by the Employer.

**6. METHOD OF PAYMENT**

- a) Subject to any special terms agreed in writing between the Employer and the Consultant the Consultant shall be entitled to invoice the Employer for the price of the Services on or at any time after the Services have been completed.
- b) The Employer undertakes to pay the Consultant within 28 days of the date of the Consultant's invoice. The time of payment of the price shall be of the essence of the Contract.
- c) Failure by the Employer to make payment on the due date, will entitle the Consultant to interest on the amount unpaid at 3% per annum above the base rate of Barclays Bank plc from time to time until payment in full is made and will further enable the Consultant to cancel the contract or suspend any further provision of Services to the Employer.
- d) If the Consultant fails to perform the Services for any reason other than any cause beyond the Consultant's reasonable control or the Employer's fault and the Consultant is accordingly liable to the Employer, the Consultant's liability shall be limited to the excess (if any) of the cost to the Employer (in the cheapest available market) of services to replace those not completed over the price of the Services.

**7. DISPUTES**

- a) Where disputes arising from the Contract cannot be resolved by the Employer and the Consultant, then an independent single arbitrator agreeable to both parties (or in default of agreement nominated on the application of either party by the Chairman of the Professional Committee of the Arboricultural Association for the time being) shall be employed.
- b) The losing party will pay the resulting costs, unless otherwise decided by the arbitrator.
- c) The Contract shall be governed by the Laws of England.

**8. THE SITE**

Access

- i) The Consultant will have free and reasonable access within the Site. Any areas that are to be excluded from this should be notified in writing to the Consultant prior to the date on which the Services are commenced.
- ii) The Employer shall ensure that the Consultant has access to private areas outside the site reasonably necessary in order that the Services can be carried out.
- iii) The Employer shall indemnify the Consultant against any liability incurred by the Consultant (of whatsoever nature) due to his having entered on private areas without permission of the owner when the Employer has stated free access has been negotiated.

**9. LIABILITY**

- a) The Consultant shall not be liable to the Employer or be deemed to be in breach of the Contract by reason of any delay in performing the Services, if the delay or failure was due to any cause beyond the Consultant's reasonable control. Without prejudice to the generality of the foregoing, the following shall be regarded as causes beyond the Consultant's reasonable control:
  - i) Act of God, explosion, flood, tempest, fire or accident;
  - ii) acts, restrictions, regulations, bye-laws, prohibitions or measures of any kind on the part of any governmental, parliamentary or local authority;
  - iii) strikes, lock-outs or other industrial actions or trade disputes.
- b) The Consultant shall not be responsible or liable for any work undertaken as a result of recommendations by the Consultant unless, or until, such work is carried out and both supervised and approved by the Consultant.

**10. QUOTATION**

- a) Any quotation given by the Consultant to the Employer shall remain open for acceptance for 30 days from the date of such quotation and thereafter lapses automatically.
- b) Acceptance of such quotation involves acceptance of these conditions. It should be noted that any attempted or actual cancellation thereof by the Employer may involve the Employer in a claim for recovery by the Consultant of any loss or expense incurred as a result.
- c) The Consultant is the owner of the copyright existing in any such quotation and it shall not be copied without the prior written consent of the Consultant. Any reproduction before obtaining the Consultant's consent constitutes an infringement of copyright and a breach of the Contract entitling the Consultant inter alia to rescind the Contract and rendering the Employer liable for payment of damages.

**11. INSOLVENCY OF EMPLOYER**

This clause applies if:

- a) the employer makes any voluntary arrangement with its creditors or becomes subject to an administration order or (being an individual or firm) becomes bankrupt or (being a company) goes into liquidation (otherwise than for the purposes of amalgamation or reconstruction); or
- b) an encumbrancer takes possession, or a receiver is appointed, of any of the property or assets of the Employer; or
- c) the Employer ceases, or threatens to cease, to carry on business; or
- d) the Consultant reasonably apprehends that any of the events mentioned above is about to occur in relation to the Employer and notifies the Employer accordingly.


If this clause applies then without prejudice to any other right or remedy available to the Consultant, the Consultant shall be entitled to cancel the Contract or suspend any further provision of Services under the Contract without any liability to the Employer, and if the services have been completed but not paid for the price shall become immediately due and payable notwithstanding any previous agreement or arrangement to the contrary.

**12. OWNERSHIP/COPYRIGHT**

The Consultant is the owner of the copyright in any report tender documentation and/or recommendations and all associated information submitted to the Employer by the Consultant. The report recommendations tender documentation and all associated information submitted to the Employer shall not be copied without prior written consent of the Consultant. Any reproduction before obtaining the Consultant's consent constitutes an infringement of copyright and a breach of the Contract entitling the Consultant, inter alia, to rescind the Contract and rendering the Employer liable for payment of damages.

**13. GENERAL**

- a) Any notice required or permitted to be given by either party to the other under these Conditions shall be in writing addressed to that other party at its registered office or principal place of business or such other address as may at the relevant time have been notified pursuant to this provision to the party giving notice.
- b) No waiver by the Consultant of any breach of the Contract by the Employer shall be considered as a waiver of any subsequent breach of the same or any other provision.
- c) If any provision of these conditions is held by any competent authority to be invalid or unenforceable in whole or in part the validity of the other provisions of these Conditions and the remainder of the provision in question shall not be affected thereby.
- d) The headings in these Conditions are for convenience only and shall not affect their interpretation.



0 2.5 5 7.5 10 12.5m  
Scale 1:250



General Notes

- LEGEND**
- AREA
  - GROUP
  - HEDGE
  - WOOD
  - TRUNK LOCATION
  - TREE SHADE (24 hr)
  - A1 AREA REFERENCE
  - G1 GROUP REFERENCE
  - H1 HEDGE REFERENCE
  - T1 TREE REFERENCE
  - W1 WOOD REFERENCE
  - B2 CATEGORY GRADE
  - TREE CANOPY GRADES
    - CATEGORY A
    - CATEGORY B
    - CATEGORY C
    - CATEGORY U
    - ROOT PROTECTION AREA

No.	Revision/Issue	Date

  
**IAIN TAVENDALE F.Arbor.A.**  
ARBORICULTURAL CONSULTANT



Follow us on LinkedIn

Project Name and Address

**Former Orgill School,  
Croaddala Avenue,  
Egremont**

Drawn by <b>www.YourCad.co.uk</b>	Checked <b>IT</b>
Date <b>September 2020</b>	
Scale <b>1:250 @ A1</b>	