

- DO NOT SCALE -

## Notes

- 1. The contractor is to check all dimensions and levels and report any errors or omissions to the Engineer
- 2. This drawing is to be read only in conjunction with all contract documents
- 3. All concrete for foundation to kerb channels and edgings shall be class ST1 (BS 5328) unless shown otherwise.
- 4. All kerbs and channels shall be hydraulically pressed and comply in all respects with BS EN 1340:2003
- 5. Kerbs and channels shall be laid true to line and level and shall not be backed up until inspected and approved by the Engineer.
- 6. All concrete for manholes, gullies and pipe/duct surrounds shall be class ST4. Unless noted otherwise.
- 7. Where possible all subbases used in the formation of roads, pavements, feature paving, mastertint etc shall be composed of recycled materials but not including any argillaceous rock, slag, unburnt colliery spoil and chalk (Specification for Highway Works table 6 /1)
- 8. Bituminous mixtures for sufacing to roads & footpaths are to conform in all respects

## Capping Requirements

	CBR Value (%)	Thickness of Capping Layer (mi			
	> 15%	0			
	> 5% < 15%	0 (with 320mm Type 1)			
	> 2.5% - 5%	210 (with 240mm Type 1)			
	< 2.5%	600 or Specialist Design			

Contractor to undertake CBR testing @ 10m intervals along road and advise of results.

Note: Where levels are raised above existing ground level. All fill beneath hardstanding formation to be 6F5.

Issued for Information	JJH	P02	JC	07.09.2022
Issued for Comment	ZW	P01	JC	26.08.2022
AMENDMENT	BY	REV	СНК	DATE

Rev P = Preliminary T = Tender C = Construction LCI = Last Construction Issue

In instances where this drawing completes or partly completes a contract, Billinghurst George & Partners will consider that it's product has been validated, unless in a period not exceeding 90 working days, the client advises to the contrary.



## Billinghurst George & Partners

CIVIL & STRUCTURAL ENGINEERS | BUILDING SURVEYORS 1st Floor, Wellington House, Wellington Court, Stockton-on-Tees, TS18 3TA T 01642 876 470 🎳 @BGPconsulting E consulting@bgp-teesside.co.uk - W www.bgp-consulting.co.uk

Copeland Borough Council

Project	Project No.						
Cleator Moor Innovation Quarter	21T2034						
Drawing Title							
BOC - External Works Details Sheet 2 of 2							

04116

Aug 2022 **Type** Role C Location Originator Volume Level

XX

CMIQ BGP File Reference

CMIQ-BGP-04-XX-DR-C-90.4-04116

04