



CROSS SECTION A - AA 1:50

NOTES:

No foul drainage connection required for proposal

No new hardstanding or impermeable surfacing is proposed

Existing levels as shown on drawing will not be altered

Ground levels on existing tarmac car park and hardstanding areas fall from north to south and surface water currently runs off into adjacent soft ground.

A retrofit sustainable drainage feature is proposed to enhance surface drainage: swales, 2m width x 200mm depth as shown in Section A - AA, to be constructed along southern edge of car park and hardstanding area

Ground conditions are suitable for infiltration: British Geological Survey (Geolndex Report) indicates superficial deposits as Glaciofluvial Deposits, Devensian - Sand and Gravel

SCALE @ A2

As shown

DRAWN BY

LR

DO not dimension off drawings.
The contractor must check all dimensions on site.
All discrepancies must be reported to the project architect immediately.

Distington Community Garden



GROUNDWORK N E & CUMBRIA

Linthorpe Cemetery Lodge
Burlam Road
Linthorpe
Middlesbrough TS5 5AP

Tel: (01642) 815 663 Fax: 01642 818 024