

FLOSH MEADOWS, CLEATOR, SR12A AND TOP MEADOWS

Drainage Strategy

Issue Date:

09 June 2023

Report Number:

1842-DS11

Client:

Lakeland Associates
(Cleator) Ltd

Revision:

D

Contents

1. Introduction 1

2. Site location, Existing Topography, Geology and Proposals 2

3. Surface and foul Water Disposal 6

4. References 11

- Appendix A – Topographical Survey
- Appendix B – Proposed Site Layout
- Appendix C – Existing Drainage Layout
- Appendix D – Greenfield Runoff Calculations
- Appendix E – Drainage Strategy and Calculations

Executive Summary

Site Location	The site is located off A5086, Cleator, CA23 3EP (nearest) at NGR 301752E 514082N. The overall development footprint measures approximately 3.30 Ha, entirely greenfield.
Site Proposals	The site is proposed to be developed with residential units.
Ground Conditions	The site is located in an area underlain by drift deposits consisting of soft - stiff clays. Surface water cannot be discharged utilising infiltration techniques.
Nearest Watercourse	The River Ehen is located 300m to the south of the overall site boundary beyond third party land. It is not possible to make a direct connection to a water course to dispose of surface water.
Nearest water feature	Within the development site, an historic man-made culverted mill race flows from north to south and outfalls via a culvert below the public highway located to the south. The mill race conveys flows from agricultural land located to the north of the development site. Surface water should discharge to the surface water feature. Surface water discharge should be restricted to a greenfield rate matching Qbar for the development, in this case 32 litres/sec.
Nearest Surface Water Sewer.	Adjacent to proposed site entrance, discharging within 40m of the head of the run to a UU combined sewer at A5086. Another surface water sewer is located within Howthorne Fields to the south of Flish Meadows. Neither sewer is suitable for disposal of surface water. The reasons are covered in greater detail within section 3.0.
Nearest Combined Sewer	On site adjacent to southern boundary
Nearest Foul Water Sewer	Adjacent to proposed site entrance, discharging within 40m to a UU combined sewer at A5086
SUDS	Pipes, flow control

The above summary should not be used in isolation and reference should be made to the full report which provides a detailed assessment of the risks affecting the development.

1. Introduction

Coast Consulting Engineers have been commissioned by Lakeland Associates (Cleator) Ltd to produce a drainage strategy to accompany a planning application for a proposed development at Flish Meadows, Cleator. This strategy is produced only for the phases known as SR12A Mid Meadows (4/17/2214) and Top Meadows (4/17/2390), although the strategy also references the wider site, as the drainage from SR12A and Top Meadows discharges into the phase known as SR12, The Meadows. This Assessment is reviewed in accordance with the National Planning Policy Framework (NPPF) for Development and Flood Risk.

A flood risk assessment has previously been completed by RWO Associates reference RO/14016.200 Version 3, dated October 2017 and has subsequently been approved. As such, this report does not assess flood risk to the proposed development.

2. Site location, Existing Topography, Geology and Proposals

2.1 Site Location

The site is located off A5086, Cleator, CA23 3EP (nearest) at NGR 301752E 514082N. The entire development footprint measures approximately 3.30 Ha, entirely greenfield.

The site location is indicated in Figure 2.11 and the proposed phasing in Figure 2.12 below.




Figure 2.11 – Site Location




Figure 2.12 – Proposed Phasing

2.2 Existing Topography

A topographical survey of the site has been undertaken and is included in Appendix A. The overall development site generally falls in a southerly direction. Site levels range from approximately 67.50m AOD at the north of SR12A to 63.00m AOD at the southern extents of SR12.

The surrounding area is developed as follows:

North: Agricultural Land
East: Agricultural Land and residential properties
South: Residential properties
West: Agricultural Land

Figure 2.21 below extracted from Google maps shows the existing site.



Figure 2.21 – Satellite image of the existing site.

2.3 Existing sewers and watercourses

A combined sewer is located within the development land, adjacent to the southern boundary line of SR12. Adopted foul and surface water sewers are located within Flish Meadows, adjacent to the proposed site entrance, the head of each run is located at the proposed site entrance. The adopted surface water and foul sewers outfall into a combined sewer approximately 40m downstream of the head of each run. All sewers are owned and maintained by United Utilities Ltd (UU). Figure 2.31 below shows the location of the existing public sewers within the vicinity of the site.

Within the overall development site, an historic man-made culverted mill race flows from north to south and outfalls via a culvert below the public highway located to the south of SR12. The mill race conveys flows from agricultural land located to the north of SR12A. Figure 2.32 overleaf shows the location of the natural watercourses within the vicinity of the site. Please also refer to Appendix C for further information on the existing drainage regime.

The River Ehen is located approximately 300m to the south of the site boundary, beyond third party land.




Figure 2.31 – sewers.




Figure 2.32 – watercourses.

2.4 Geology

A phase 2 intrusive investigation of ground conditions has been completed by Geo Environmental Engineering Ltd, reference 2018-3167 dated 09.08.2018. The report states that the site is underlain by varying ground conditions, largely comprising soft to stiff clays. Ground water was encountered across the site at depths of between 1.50m to 2.90m.

2.5 Development Proposals

The site is proposed to be developed with residential units. A copy of the proposed architectural site layout can be found in Appendix B.


3. Surface Water Disposal

3.1 Existing Surface Water Drainage

There are no existing sewers serving the greenfield site.

An existing historic, man-made, culverted, mill race flows through the site from north to south. The race outfalls from the development via a culvert below the public highway located to the south of SR12. The race is not a natural watercourse and is not identified on GroundSure plans (ref figure 2.32) above or historic Pre 1800's mining plans (ref figure 3.11) below.

Please also refer to Appendix C for further information on the existing drainage regime.



3.2 Proposed Surface Water Drainage

In line with national standards, consideration has been given to the preferred hierarchy for disposal of surface water from the development, as contained in Part H of the Building Regulations. The hierarchy is as follows:

1. By infiltration
2. To watercourse
3. To sewer

As noted earlier, superficial deposits comprise of soft - stiff clays with a low permeability. It is considered that utilisation of infiltration techniques will not be applicable for the proposed development.

The nearest watercourse to the development is located approximately 300m to the south of the site boundary, beyond third party land. As such, it will not be possible to make a direct connection to a watercourse.

Following discussions between the developer and the LLFA, it has been agreed to discharge surface water to the Mill Race located within the site boundary.

3.3 SUDS Techniques

In line with National Planning Policy, SUDS techniques will be utilised as part of the design of the surface water network. The applicable techniques and the benefits that they bring to the development are outlined below.

- Flow control: A vortex flow control device will be utilised to restrict flows to the equivalent of existing site greenfield rate (Qbar)
- Surface water conveyance: Surface water will be conveyed through the development utilising below ground pipes.
- Surface water treatment: Attenuated surface water flows will be stored in a piped network.

3.4 SuDS Maintenance

Regular inspection and maintenance is key to the effective operation of SuDS features. Maintenance responsibility for SuDS features proposed as part of the development is to be placed with a responsible organisation and in this case a nominated management and maintenance company.

Removal of debris and any settled silt from SuDS features is the key maintenance requirement for the continued effective operation of the SuDS features. Most of the maintenance activities can be undertaken as part of regular landscape maintenance activities.

3.5 Post Development Discharge Rate

Proposed surface water discharge rates will be limited from the development to the equivalent of the pre-development Qbar green field run off rate, for all storms up to and including 1 in 100 year return period rainfall event + 40% increase in rainfall intensity to account for the predicted effects of climate change.

In line with national and local standards the greenfield run off rate for 3.30 Ha of developed land has been calculated using the Institute of Hydrology (IH) Report 124 Flood Estimation for Small Catchments (1994) method, with flow rate linearly interpolated due to site being smaller than 50Ha. HR Wallingford Greenfield runoff rate estimation for sites tool, available at <https://www.uksuds.com> has been used to calculate Qbar run off rate at 32.02 l/sec. An assessment of the allowable discharge rate is outlined below in figure 3.51.

Greenfield runoff rates		
	Default	Edited
QBAR (l/s):	32.02	32.02
1 in 1 year (l/s):	27.85	27.85
1 in 30 years (l/s):	54.43	54.43
1 in 100 year (l/s):	66.59	66.59
1 in 200 years (l/s):	75.88	75.88

This report was produced using the greenfield runoff tool developed by HR Wallingford and available at www.uksuds.com. The use of this tool is subject to the UK SUDS terms and conditions and licence agreement, which can both be found at www.uksuds.com/terms-and-conditions.htm. The outputs from this tool are estimates of greenfield runoff rates. The use of these results is the responsibility of the users of this tool. No liability will be accepted by HR Wallingford, the Environment Agency, CEH, Hydrosolutions or any other organisation for the use of this data in the design or operational characteristics of any drainage scheme.

Figure 3.51 Greenfield run off rates.

Please refer to Appendix D for further information on green field run off rates.

Note – the ‘developed land’ includes for all phases of the proposed development.

3.6 Surface Water Attenuation

Surface water will be restricted for all events up to an including the 100 year event with a 50% allowance for climate change and a 10% allowance for urban creep. Attenuated flows will be contained on site within a designated storage system. Please refer to the calculations and drainage strategy contained within Appendix E.

Note – the allowable discharge rate and drainage calculations include for all phases of the development.

By restricting the peak rate of discharge from the site Qbar to the watercourse for all events up to and including the 100-year event, **the proposed development will provide betterment from the existing regime in line with the table below.**

Return period	greenfield rate	Proposed	Betterment
Qbar	32.02 l/s	32.0 l/s	0%
30	54.43 l/s	32.0 l/s	31%
100	66.59 l/s	32.0 l/s	52%
100+50%	99.85 l/s	32.0 l/s	68%

3.7 Proposed Foul Drainage

It is proposed to discharge a portion of the foul water to the adjacent UU combined sewer and a portion to the existing foul sewer in Flosch Meadows, both via gravity connections.

4. References

The following reference documents have been used in the preparation of this report.

- National Planning Policy Framework 2021.
- PPG 2021.
- Environment Agency online flood maps.
- Sewers for Adoption 6th Edition - WRC plc, April 2006.
- Building Regulations Document H 2010.
- Improving the Flood Performance of New Buildings – Defra.
- Rainfall runoff management for developments SC030219 – Defra.
- Susdrain.org
- The SuDS Manual CIRIA C753.

Appendices

Appendix A



UTILITY KEY

LINE TYPE			
BT BELONG GROUND		WATER BELONG GROUND	
BT ABOVE GROUND		WATER ABOVE GROUND	
BT ASSIGNED ROUTE		WATER ASSIGNED ROUTE	
CATY BELONG GROUND		UNKNOWN BELONG GROUND	
CATY ABOVE GROUND		UNKNOWN ABOVE GROUND	
CATY ASSIGNED ROUTE		UNKNOWN ASSIGNED ROUTE	
COMB BELONG GROUND		COMB BELONG GROUND	
COMB ABOVE GROUND		COMB ABOVE GROUND	
COMB ASSIGNED ROUTE		ASSIGNED COMBING WATER SEWER ROUTE	
GAS BELONG GROUND		SOIL WATER SEWER	
GAS ABOVE GROUND		ASSIGNED FLOW WATER SEWER ROUTE	
GAS ASSIGNED ROUTE		STORM WATER SEWER	
EG (ASSIGNED ROUTE)		ASSIGNED STORM WATER SEWER ROUTE	
ELECTRIC BELONG GROUND		REINSTATEMENT SOAR	
ELECTRIC ABOVE GROUND		SURVEY BOUNDARY	
ELECTRIC ASSIGNED ROUTE			


[illegible][illegible]

NOTES



SiteScan
Information to build on

LAND AT FLOSH MEADOWS
CLEATOR
CUMBRIA

[illegible]

DISCLAIMER

Unless otherwise stated, all scenarios shown on this plan have been surveyed using approved detectors and the connections and orientations mentioned. First noticed, unless otherwise stated, is correct.

No guarantee is made that the information shown on this plan is a true and accurate representation of all the features of the site. It is not intended that the depth accuracy for the underground utilities should be $\pm 15\%$ of depth.

Utilities listed using GPR techniques show depths approximately from ground level to the top of the utility. Utilities listed using other methods show depths approximately from the surface of the ground to the top of the utility.

Electricity and gas are shown in red. All other utilities are shown in blue. The contents of the utility, including gas, electricity and water, are not shown. The depth of the utility is shown in blue.

Where the surveys are shown as 'Taken From Records' on the drawing are not reliable for any less than they may state due to a lack of accuracy in the original records.

Due to B7's policy we are not permitted to take this inspection chamber cover off.

Reference should be made to the methodology used and as detailed within the HSE V14 (Assessing Design of Surface Structures to Utility Location) leaflet.

It is important to remember that all excavations are to be carried out in accordance with the M18 V14 (Assessing Design from Underground Structures) leaflet.

Plan accuracies of the order of $\pm 100\text{mm}$ may be achieved but the figure will depend on the depth of the service below ground and the nature and position of the service. In other positions, separation may be possible. Separation of free-standing pipes may be limited.

Existing recorded information showing underground services is not comprehensive and difficult to access. It should be regarded as only a guide to the location of services.

NOTES

C S A	SURVEY EXTENDED DAMAGE SURVEYED INITIAL RELEASE	NP NP NP	NG NG NG
REV	AMENDMENT		DRAWN CHECKED

SUITE 5 VITA HOUSE
FISH QUAY
NORTH SHIELDS
NE30 1JA
T: 0191 257 2911
www.sitescanltd.com

RICHARD MULHOLLAND			
LAND AT FLOSH MEADOWS CLEATOR CUMBRIA			
TOPOGRAPHICAL SURVEY			
DRAWING TITLE			
1:500 @ A1	DATE 18.03.14	OSTN02	
APPROVED BY NP	PREPARED BY NP	CHECKED BY NG	
P14053		2/2	C
DRAWN BY	CHECKED BY	REV	

Appendix B




St Mary's Church
Cemetery & 1927
Lourdes replica Grotto

HEDGE KEY
NEW HAWTHORN HEDGE
DOUBLE LAYER OF WHIPS
PLANTED AT 6 U/M HEIGHT
40x40cm
MATERIALS SCHEDULE
Driveway - Permeable block paving 100x200mm
Colour - Dark grey
Patios and paving to rear - Concrete pre-cast concrete
Flag 50x500mm
Paths to front - Indian Stone random pattern / size
PARKING BAY SIZES 2500 x 5000mm

Issue -		
PLANNING		
Client -		
Mr & Mrs Mulholland		
Project -		
Housing Development		
location / Postcode / what3words		
Flish Meadows, Cleator, Cumbria, CA14 0QP		
media, others, logbook		
Drawing Title - Proposed Site Plan - SR12, SR12A & Top Meadow		
Job No -	1236	Dwg No - 20
DATE	10 Oct 2021	Scale- 1:500
B:\tnap3721042191.png	RIBA Chartered ARCHITECTS	Rev 1 Paper A0
E - greenswallow@btinternet.com		
M - 017530 964114		
Registered Office - Green Swallow North Limited		
Swallow Barn, Blinderake, Cumbria, CA14 0QP		
DIMENSIONS TO BE CHECKED ON SITE		
FIGURED DIMENSIONS TO BE TAKEN IN		
PREFERENCE TO SCALED DIMENSIONS		
copyright Green Swallow North Limited		

Appendix C



LEGEND	
	LAND DRAINAGE
	UU COMBINED WATER SEWER
	UU FOUL WATER SEWER
	UU SURFACE WATER SEWER

P3	19-05-21	Updated to reflect client comments	RH	RH	PL
P2	25-04-21	Updated to reflect client comments	RH	RH	PL
P1	22-04-21	Preliminary issue	RH	RH	PL
Issue	Date	Description	By	Chkd	Appd



7 Silverton Court, Northumberland Business Park, NE23 7RY
0191 5977879

Client
MR R.W. MULHOLLAND

Job Title
FLOSS MEADOWS
CUMBRIA

Drawing Title
EXISTING DRAINAGE

Scale of A0
1:250

Drawing Status
PRELIMINARY

Job No
1842

Drawing No
201

Issue
P3

Appendix D

Calculated by:	<input type="text" value="richard hall"/>
Site name:	<input type="text" value="Flosh Meadows"/>
Site location:	<input type="text" value="Cleator"/>

This is an estimation of the greenfield runoff rates that are used to meet normal best practice criteria in line with Environment Agency guidance "Rainfall runoff management for developments", SC030219 (2013), the SuDS Manual C753 (Ciria, 2015) and the non-statutory standards for SuDS (Defra, 2015). This information on greenfield runoff rates may be the basis for setting consents for the drainage of surface water runoff from sites.

Site Details

Latitude:	<input type="text" value="54.51164° N"/>
Longitude:	<input type="text" value="3.51942° W"/>
Reference:	<input type="text" value="2032601581"/>
Date:	<input type="text" value="May 28 2021 13:23"/>

Runoff estimation approach

Site characteristics

Total site area (ha):	<input type="text" value="3.30"/>
-----------------------	-----------------------------------

Methodology

Q _{BAR} estimation method:	<input type="text" value="Calculate from SPR and SAAR"/>
SPR estimation method:	<input type="text" value="Calculate from SOIL type"/>

Soil characteristics

	Default	Edited
SOIL type:	<input type="text" value="4"/>	<input type="text" value="4"/>
HOST class:	<input type="text" value="N/A"/>	<input type="text" value="N/A"/>
SPR/SPRHOST:	<input type="text" value="0.47"/>	<input type="text" value="0.47"/>

Hydrological characteristics

	Default	Edited
SAAR (mm):	<input type="text" value="1271"/>	<input type="text" value="1271"/>
Hydrological region:	<input type="text" value="10"/>	<input type="text" value="10"/>
Growth curve factor 1 year:	<input type="text" value="0.87"/>	<input type="text" value="0.87"/>
Growth curve factor 30 years:	<input type="text" value="1.7"/>	<input type="text" value="1.7"/>
Growth curve factor 100 years:	<input type="text" value="2.08"/>	<input type="text" value="2.08"/>
Growth curve factor 200 years:	<input type="text" value="2.37"/>	<input type="text" value="2.37"/>

Notes

(1) Is $Q_{BAR} < 2.0$ l/s/ha?

When Q_{BAR} is < 2.0 l/s/ha then limiting discharge rates are set at 2.0 l/s/ha.

(2) Are flow rates < 5.0 l/s?

Where flow rates are less than 5.0 l/s consent for discharge is usually set at 5.0 l/s if blockage from vegetation and other materials is possible. Lower consent flow rates may be set where the blockage risk is addressed by using appropriate drainage elements.

(3) Is $SPR/SPRHOST \leq 0.3$?


Where groundwater levels are low enough the use of soakaways to avoid discharge offsite would normally be preferred for disposal of surface water runoff.

Greenfield runoff rates


	Default	Edited
Q _{BAR} (l/s):	<input type="text" value="32.02"/>	<input type="text" value="32.02"/>
1 in 1 year (l/s):	<input type="text" value="27.85"/>	<input type="text" value="27.85"/>
1 in 30 years (l/s):	<input type="text" value="54.43"/>	<input type="text" value="54.43"/>
1 in 100 year (l/s):	<input type="text" value="66.59"/>	<input type="text" value="66.59"/>
1 in 200 years (l/s):	<input type="text" value="75.88"/>	<input type="text" value="75.88"/>


This report was produced using the greenfield runoff tool developed by HR Wallingford and available at www.uksuds.com. The use of this tool is subject to the UK SuDS terms and conditions and licence agreement, which can both be found at www.uksuds.com/terms-and-conditions.htm. The outputs from this tool are estimates of greenfield runoff rates. The use of these results is the responsibility of the users of this tool. No liability will be accepted by HR Wallingford, the Environment Agency, CEH, Hydrosolutions or any other organisation for the use of this data in the design or operational characteristics of any drainage scheme.

Appendix E


















Do not scale				Drawing Title				Client				Drawing Title			
								MR R.W. MULHOLLAND				IMPERMEABLE AREAS			
				7 Silvertown Court, Northumberland Business Park, NE23 7RY				Job Title				Scale at A0			
								FLOSH MEADOWS CUMBRIA				Drawing Status			
												TENDER			
												Job No			
												Drawing No			
												Issue			
												1842			
												121			
												T3			



Coast Consulting Engineers Ltd		Page 0
Suite 6, Vita House	FLOSH MEADOWS	
Fish Quay	CLEATOR	
North Shields NE30 1JA	1:2	
Date 09/06/2023	Designed by RH	
File 230609 REVISED SURFACE W...	Checked by PL	
Innovyze	Network 2020.1	


STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for 180518 SW1.SWS

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	41.957	0.105	399.6	0.061	5.00	0.0	0.600	o	975	Pipe/Conduit	
1.001	53.639	0.134	400.3	0.118	0.00	0.0	0.600	o	975	Pipe/Conduit	
1.002	31.512	0.185	170.3	0.129	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.003	25.483	0.150	169.9	0.104	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.004	17.652	0.104	169.7	0.035	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.005	18.982	0.112	169.5	0.028	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.006	13.655	0.080	170.7	0.029	0.00	0.0	0.600	o	225	Pipe/Conduit	
2.000	71.706	0.221	324.5	0.115	5.00	0.0	0.600	o	525	Pipe/Conduit	
2.001	37.730	0.116	325.3	0.225	0.00	0.0	0.600	o	525	Pipe/Conduit	
2.002	22.253	0.068	325.0	0.065	0.00	0.0	0.600	o	375	Pipe/Conduit	
2.003	33.218	0.102	325.7	0.065	0.00	0.0	0.600	o	375	Pipe/Conduit	
2.004	13.246	0.041	323.1	0.062	0.00	0.0	0.600	o	375	Pipe/Conduit	
2.005	14.105	0.043	328.0	0.042	0.00	0.0	0.600	o	375	Pipe/Conduit	
1.007	24.092	0.074	325.6	0.021	0.00	0.0	0.600	o	375	Pipe/Conduit	
1.008	21.726	0.067	324.3	0.029	0.00	0.0	0.600	o	375	Pipe/Conduit	




Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	0.00	5.43	63.013	0.061	0.0	0.0	0.0	1.64	1225.0	0.0
1.001	0.00	5.97	62.908	0.179	0.0	0.0	0.0	1.64	1223.9	0.0
1.002	0.00	6.50	62.774	0.308	0.0	0.0	0.0	1.00	39.7	0.0
1.003	0.00	6.92	62.589	0.412	0.0	0.0	0.0	1.00	39.8	0.0
1.004	0.00	7.22	62.439	0.447	0.0	0.0	0.0	1.00	39.8	0.0
1.005	0.00	7.53	62.335	0.475	0.0	0.0	0.0	1.00	39.8	0.0
1.006	0.00	7.76	62.223	0.504	0.0	0.0	0.0	1.00	39.7	0.0
2.000	0.00	5.97	62.586	0.115	0.0	0.0	0.0	1.24	268.0	0.0
2.001	0.00	6.47	62.365	0.340	0.0	0.0	0.0	1.24	267.7	0.0
2.002	0.00	6.85	62.249	0.405	0.0	0.0	0.0	1.00	110.4	0.0
2.003	0.00	7.40	62.181	0.470	0.0	0.0	0.0	1.00	110.3	0.0
2.004	0.00	7.62	62.079	0.532	0.0	0.0	0.0	1.00	110.7	0.0
2.005	0.00	7.86	62.038	0.574	0.0	0.0	0.0	0.99	109.9	0.0
1.007	0.00	8.26	61.993	1.099	0.0	0.0	0.0	1.00	110.3	0.0
1.008	0.00	8.62	61.919	1.128	0.0	0.0	0.0	1.00	110.5	0.0

Coast Consulting Engineers Ltd										Page 1	
Suite 6, Vita House Fish Quay North Shields NE30 1JA					FLOSH MEADOWS CLEATOR 1:2						
Date 09/06/2023					Designed by RH						
File 230609 REVISED SURFACE W...					Checked by PL						
Innovyze					Network 2020.1						

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for 180518 SW1.SWS

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
3.000	15.459	0.048	322.1	0.070	5.00	0.0	0.600	o	375	Pipe/Conduit	
1.009	26.775	0.109	245.6	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
1.010	3.900	0.016	243.8	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
3.000	0.00	5.26	61.900	0.070	0.0	0.0	0.0	1.00	110.9	0.0
1.009	0.00	9.07	61.852	1.198	0.0	0.0	0.0	1.00	70.6	0.0
1.010	0.00	9.13	61.743	1.198	0.0	0.0	0.0	1.00	70.9	0.0

Free Flowing Outfall Details for 180518 SW1.SWS

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D, L (mm)	W (mm)
1.010	C1	63.006	61.727	61.727	1350	0

Simulation Criteria for 180518 SW1.SWS


Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1


Number of Input Hydrographs	0	Number of Storage Structures	13
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0


Synthetic Rainfall Details

Rainfall Model	FSR	M5-60 (mm)	19.600
Return Period (years)	2	Ratio R	0.223
Region		England and Wales	Profile Type Summer

©1982-2020 Innovyze

Coast Consulting Engineers Ltd		Page 2
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:2	
Date 09/06/2023 File 230609 REVISED SURFACE W...	Designed by RH Checked by PL	
Innovyze Network 2020.1		
<div>Synthetic Rainfall Details</div> <div>Cv (Summer) 0.750 Storm Duration (mins) 30 Cv (Winter) 0.840</div>		
©1982-2020 Innovyze		


Coast Consulting Engineers Ltd		Page 3																																																																																										
Suite 6, Vita House	FLOSH MEADOWS																																																																																											
Fish Quay	CLEATOR																																																																																											
North Shields NE30 1JA	1:2																																																																																											
Date 09/06/2023	Designed by RH																																																																																											
File 230609 REVISED SURFACE W...	Checked by PL																																																																																											
Innovyze	Network 2020.1																																																																																											
<div>Online Controls for 180518 SW1.SWS</div> <div>Hydro-Brake® Optimum Manhole: 3 HB, DS/PN: 1.002, Volume (m³): 45.9</div> <div><div>Unit Reference MD-SHE-0107-7000-2119-7000</div><div>Design Head (m)2.119</div><div>Design Flow (l/s)7.0</div><div>Flush-Flo™Calculated</div><div>ObjectiveMinimise upstream storage</div><div>ApplicationSurface</div><div>Sump AvailableYes</div><div>Diameter (mm)107</div><div>Invert Level (m)62.774</div><div>Minimum Outlet Pipe Diameter (mm)150</div><div>Suggested Manhole Diameter (mm)1200</div></div> <div><table><tr><th>Control Points</th><th>Head (m)</th><th>Flow (l/s)</th><th>Control Points</th><th>Head (m)</th><th>Flow (l/s)</th></tr><tr><td>Design Point (Calculated)</td><td>2.119</td><td>7.0</td><td>Kick-Flo®</td><td>0.957</td><td>4.8</td></tr><tr><td>Flush-Flo™</td><td>0.469</td><td>6.1</td><td>Mean Flow over Head Range</td><td>-</td><td>5.6</td></tr></table><p>The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated</p><table><tr><th>Depth (m)</th><th>Flow (l/s)</th><th>Depth (m)</th><th>Flow (l/s)</th><th>Depth (m)</th><th>Flow (l/s)</th><th>Depth (m)</th><th>Flow (l/s)</th></tr><tr><td>0.100</td><td>3.7</td><td>1.200</td><td>5.4</td><td>3.000</td><td>8.2</td><td>7.000</td><td>12.3</td></tr><tr><td>0.200</td><td>5.4</td><td>1.400</td><td>5.8</td><td>3.500</td><td>8.9</td><td>7.500</td><td>12.7</td></tr><tr><td>0.300</td><td>5.9</td><td>1.600</td><td>6.1</td><td>4.000</td><td>9.4</td><td>8.000</td><td>13.1</td></tr><tr><td>0.400</td><td>6.0</td><td>1.800</td><td>6.5</td><td>4.500</td><td>10.0</td><td>8.500</td><td>13.5</td></tr><tr><td>0.500</td><td>6.1</td><td>2.000</td><td>6.8</td><td>5.000</td><td>10.5</td><td>9.000</td><td>13.9</td></tr><tr><td>0.600</td><td>6.0</td><td>2.200</td><td>7.1</td><td>5.500</td><td>11.0</td><td>9.500</td><td>14.3</td></tr><tr><td>0.800</td><td>5.6</td><td>2.400</td><td>7.4</td><td>6.000</td><td>11.4</td><td></td><td></td></tr><tr><td>1.000</td><td>4.9</td><td>2.600</td><td>7.7</td><td>6.500</td><td>11.9</td><td></td><td></td></tr></table><div>Hydro-Brake® Optimum Manhole: 10 HB, DS/PN: 2.002, Volume (m³): 13.2</div><div><div>Unit Reference MD-SHE-0107-6000-1575-6000</div><div>Design Head (m)1.575</div><div>Design Flow (l/s)6.0</div><div>Flush-Flo™Calculated</div><div>ObjectiveMinimise upstream storage</div><div>ApplicationSurface</div><div>Sump AvailableYes</div><div>Diameter (mm)106</div><div>Invert Level (m)62.249</div><div>Minimum Outlet Pipe Diameter (mm)150</div></div></div> <div>©1982-2020 Innovyze</div>			Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)	Design Point (Calculated)	2.119	7.0	Kick-Flo®	0.957	4.8	Flush-Flo™	0.469	6.1	Mean Flow over Head Range	-	5.6	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	0.100	3.7	1.200	5.4	3.000	8.2	7.000	12.3	0.200	5.4	1.400	5.8	3.500	8.9	7.500	12.7	0.300	5.9	1.600	6.1	4.000	9.4	8.000	13.1	0.400	6.0	1.800	6.5	4.500	10.0	8.500	13.5	0.500	6.1	2.000	6.8	5.000	10.5	9.000	13.9	0.600	6.0	2.200	7.1	5.500	11.0	9.500	14.3	0.800	5.6	2.400	7.4	6.000	11.4			1.000	4.9	2.600	7.7	6.500	11.9		
Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)																																																																																							
Design Point (Calculated)	2.119	7.0	Kick-Flo®	0.957	4.8																																																																																							
Flush-Flo™	0.469	6.1	Mean Flow over Head Range	-	5.6																																																																																							
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)																																																																																					
0.100	3.7	1.200	5.4	3.000	8.2	7.000	12.3																																																																																					
0.200	5.4	1.400	5.8	3.500	8.9	7.500	12.7																																																																																					
0.300	5.9	1.600	6.1	4.000	9.4	8.000	13.1																																																																																					
0.400	6.0	1.800	6.5	4.500	10.0	8.500	13.5																																																																																					
0.500	6.1	2.000	6.8	5.000	10.5	9.000	13.9																																																																																					
0.600	6.0	2.200	7.1	5.500	11.0	9.500	14.3																																																																																					
0.800	5.6	2.400	7.4	6.000	11.4																																																																																							
1.000	4.9	2.600	7.7	6.500	11.9																																																																																							


Coast Consulting Engineers Ltd				Page 4			
Suite 6, Vita House		FLOSH MEADOWS					
Fish Quay		CLEATOR					
North Shields NE30 1JA		1:2					
Date 09/06/2023		Designed by RH					
File 230609 REVISED SURFACE W...		Checked by PL					
Innovyze		Network 2020.1					
<hr/>							
Hydro-Brake® Optimum Manhole: 10 HB, DS/PN: 2.002, Volume (m³): 13.2							
Suggested Manhole Diameter (mm) 1200							
Control Points		Head (m)	Flow (l/s)	Control Points		Head (m)	Flow (l/s)
Design Point (Calculated)		1.575	6.0	Kick-Flo®		0.952	4.7
Flush-Flo™		0.468	5.9	Mean Flow over Head Range		-	5.2
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated							
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.6	1.200	5.3	3.000	8.1	7.000	12.1
0.200	5.3	1.400	5.7	3.500	8.7	7.500	12.5
0.300	5.7	1.600	6.0	4.000	9.3	8.000	12.9
0.400	5.9	1.800	6.4	4.500	9.8	8.500	13.3
0.500	5.9	2.000	6.7	5.000	10.3	9.000	13.7
0.600	5.9	2.200	7.0	5.500	10.8	9.500	14.0
0.800	5.5	2.400	7.3	6.000	11.3		
1.000	4.9	2.600	7.6	6.500	11.7		
<hr/>							
Hydro-Brake® Optimum Manhole: 17 HB, DS/PN: 1.009, Volume (m³): 9.6							
Unit Reference MD-SHE-0235-3200-1642-3200							
Design Head (m)				1.642			
Design Flow (l/s)				32.0			
Flush-Flo™				Calculated			
Objective				Minimise upstream storage			
Application				Surface			
Sump Available				Yes			
Diameter (mm)				235			
Invert Level (m)				61.852			
Minimum Outlet Pipe Diameter (mm)				300			
Suggested Manhole Diameter (mm)				1800			
Control Points		Head (m)	Flow (l/s)	Control Points		Head (m)	Flow (l/s)
Design Point (Calculated)		1.642	32.0	Kick-Flo®		1.101	26.4
Flush-Flo™		0.503	32.0	Mean Flow over Head Range		-	27.5
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated							
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	7.8	0.200	23.7	0.300	30.6	0.400	31.7
<hr/>							
©1982-2020 Innovyze							





Micro
Drainage


Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.500	32.0	1.800	33.4	4.000	49.1	7.500	66.6
0.600	31.8	2.000	35.2	4.500	52.0	8.000	68.8
0.800	31.0	2.200	36.8	5.000	54.7	8.500	70.8
1.000	28.8	2.400	38.4	5.500	57.3	9.000	72.8
1.200	27.5	2.600	39.9	6.000	59.8	9.500	74.8
1.400	29.6	3.000	42.8	6.500	62.2		
1.600	31.6	3.500	46.1	7.000	64.4		


Coast Consulting Engineers Ltd		Page 6																																																																								
Suite 6, Vita House	FLOSH MEADOWS																																																																									
Fish Quay	CLEATOR																																																																									
North Shields NE30 1JA	1:2																																																																									
Date 09/06/2023	Designed by RH																																																																									
File 230609 REVISED SURFACE W...	Checked by PL																																																																									
Innovyze	Network 2020.1																																																																									
<div>Storage Structures for 180518 SW1.SWS</div> <div>Cellular Storage Manhole: 1, DS/PN: 1.000</div> <div>Invert Level (m) 63.585 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>51.8</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>51.8</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table> <div>Cellular Storage Manhole: 2, DS/PN: 1.001</div> <div>Invert Level (m) 63.015 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>220.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>220.0</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table> <div>Cellular Storage Manhole: 4, DS/PN: 1.003</div> <div>Invert Level (m) 62.589 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>129.5</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>129.5</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table> <div>Cellular Storage Manhole: 6, DS/PN: 1.005</div> <div>Invert Level (m) 62.335 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>25.9</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>25.9</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table>			Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	51.8	0.0	0.521	0.0	0.0	0.520	51.8	0.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	220.0	0.0	0.521	0.0	0.0	0.520	220.0	0.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	129.5	0.0	0.521	0.0	0.0	0.520	129.5	0.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	25.9	0.0	0.521	0.0	0.0	0.520	25.9	0.0			
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	51.8	0.0	0.521	0.0	0.0																																																																					
0.520	51.8	0.0																																																																								
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	220.0	0.0	0.521	0.0	0.0																																																																					
0.520	220.0	0.0																																																																								
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	129.5	0.0	0.521	0.0	0.0																																																																					
0.520	129.5	0.0																																																																								
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	25.9	0.0	0.521	0.0	0.0																																																																					
0.520	25.9	0.0																																																																								
©1982-2020 Innovyze																																																																										

Coast Consulting Engineers Ltd			Page 7																																																																										
Suite 6, Vita House Fish Quay North Shields NE30 1JA		FLOSH MEADOWS CLEATOR 1:2																																																																											
Date 09/06/2023		Designed by RH																																																																											
File 230609 REVISED SURFACE W...		Checked by PL																																																																											
Innovyze			Network 2020.1																																																																										
<p style="text-align: center;"><u>Cellular Storage Manhole: 7, DS/PN: 1.006</u></p> <p style="text-align: center;">Invert Level (m) 62.224 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>25.9</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>25.9</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 8, DS/PN: 2.000</u></p> <p style="text-align: center;">Invert Level (m) 63.413 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>77.7</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>77.7</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 9, DS/PN: 2.001</u></p> <p style="text-align: center;">Invert Level (m) 62.621 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>388.5</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>388.5</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 10 HB, DS/PN: 2.002</u></p> <p style="text-align: center;">Invert Level (m) 62.249 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>170.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>170.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 11, DS/PN: 2.003</u></p> <p style="text-align: center;">Invert Level (m) 62.181 Infiltration Coefficient Side (m/hr) 0.00000 Infiltration Coefficient Base (m/hr) 0.00000 Safety Factor 2.0</p>						Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	25.9	0.0	0.521	0.0	0.0	0.520	25.9	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	77.7	0.0	0.521	0.0	0.0	0.520	77.7	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	388.5	0.0	0.521	0.0	0.0	0.520	388.5	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	170.0	0.0	0.521	0.0	0.0	0.520	170.0	0.0			
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	25.9	0.0	0.521	0.0	0.0																																																																								
0.520	25.9	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	77.7	0.0	0.521	0.0	0.0																																																																								
0.520	77.7	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	388.5	0.0	0.521	0.0	0.0																																																																								
0.520	388.5	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	170.0	0.0	0.521	0.0	0.0																																																																								
0.520	170.0	0.0																																																																											
©1982-2020 Innovyze																																																																													

Coast Consulting Engineers Ltd			Page 8																																																																										
Suite 6, Vita House Fish Quay North Shields NE30 1JA		FLOSH MEADOWS CLEATOR 1:2																																																																											
Date 09/06/2023		Designed by RH																																																																											
File 230609 REVISED SURFACE W...		Checked by PL																																																																											
Innovyze			Network 2020.1																																																																										
<p style="text-align: center;"><u>Cellular Storage Manhole: 11, DS/PN: 2.003</u></p> <p style="text-align: center;">Porosity 0.95</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>200.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>200.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 12, DS/PN: 2.004</u></p> <p style="text-align: center;">Invert Level (m) 62.079 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>129.5</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>129.5</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 15, DS/PN: 1.008</u></p> <p style="text-align: center;">Invert Level (m) 61.919 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>30.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>30.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 16, DS/PN: 3.000</u></p> <p style="text-align: center;">Invert Level (m) 61.900 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>51.8</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>51.8</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 17 HB, DS/PN: 1.009</u></p> <p style="text-align: center;">Invert Level (m) 61.852 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p>						Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	200.0	0.0	0.521	0.0	0.0	0.520	200.0	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	129.5	0.0	0.521	0.0	0.0	0.520	129.5	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	30.0	0.0	0.521	0.0	0.0	0.520	30.0	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	51.8	0.0	0.521	0.0	0.0	0.520	51.8	0.0			
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	200.0	0.0	0.521	0.0	0.0																																																																								
0.520	200.0	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	129.5	0.0	0.521	0.0	0.0																																																																								
0.520	129.5	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	30.0	0.0	0.521	0.0	0.0																																																																								
0.520	30.0	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	51.8	0.0	0.521	0.0	0.0																																																																								
0.520	51.8	0.0																																																																											
©1982-2020 Innovyze																																																																													


Coast Consulting Engineers Ltd			Page 9																				
Suite 6, Vita House		FLOSH MEADOWS																					
Fish Quay		CLEATOR																					
North Shields NE30 1JA		1:2																					
Date 09/06/2023		Designed by RH																					
File 230609 REVISED SURFACE W...		Checked by PL																					
Innovyze		Network 2020.1																					
<p style="text-align: center;"><u>Cellular Storage Manhole: 17 HB, DS/PN: 1.009</u></p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>77.7</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>77.7</td><td>0.0</td><td></td><td></td><td></td></tr></table>						Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	77.7	0.0	0.521	0.0	0.0	0.520	77.7	0.0			
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																		
0.000	77.7	0.0	0.521	0.0	0.0																		
0.520	77.7	0.0																					
<p style="text-align: center;">©1982-2020 Innovyze</p>																							

Coast Consulting Engineers Ltd							Page 10																																																																																																																																																																
Suite 6, Vita House Fish Quay North Shields NE30 1JA				FLOSH MEADOWS CLEATOR 1:2																																																																																																																																																																			
Date 09/06/2023				Designed by RH																																																																																																																																																																			
File 230609 REVISED SURFACE W...				Checked by PL																																																																																																																																																																			
Innovyze				Network 2020.1																																																																																																																																																																			
<u>Summary of Critical Results by Maximum Level (Rank 1) for 180518 SW1.SWS</u>																																																																																																																																																																							
<u>Simulation Criteria</u>																																																																																																																																																																							
Areal Reduction Factor		1.000		Additional Flow - % of Total Flow		0.000																																																																																																																																																																	
Hot Start (mins)		0		MADD Factor * 10m³/ha Storage		2.000																																																																																																																																																																	
Hot Start Level (mm)		0		Inlet Coefficient		0.800																																																																																																																																																																	
Manhole Headloss Coeff (Global)		0.500		Flow per Person per Day (l/per/day)		0.000																																																																																																																																																																	
Foul Sewage per hectare (l/s)		0.000																																																																																																																																																																					
Number of Input Hydrographs				0		Number of Storage Structures		13																																																																																																																																																															
Number of Online Controls				3		Number of Time/Area Diagrams		0																																																																																																																																																															
Number of Offline Controls				0		Number of Real Time Controls		0																																																																																																																																																															
<u>Synthetic Rainfall Details</u>																																																																																																																																																																							
Rainfall Model		FSR		Ratio R		0.220																																																																																																																																																																	
Region England and Wales Cv (Summer)		1.000																																																																																																																																																																					
M5-60 (mm)		18.600		Cv (Winter)		1.000																																																																																																																																																																	
Margin for Flood Risk Warning (mm)				300.0																																																																																																																																																																			
Analysis Timestep				2.5 Second Increment (Extended)																																																																																																																																																																			
DTS Status				OFF																																																																																																																																																																			
DVD Status				OFF																																																																																																																																																																			
Inertia Status				OFF																																																																																																																																																																			
Profile(s)				Summer and Winter																																																																																																																																																																			
Duration(s) (mins)		15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440																																																																																																																																																																					
Return Period(s) (years)				2																																																																																																																																																																			
Climate Change (%)				0																																																																																																																																																																			
<table><tr><th colspan="2">US/MH</th><th colspan="2">Return Climate</th><th>First (X)</th><th>First (Y)</th><th>First (Z)</th><th>Overflow</th><th>Water</th></tr><tr><th>PN</th><th>Name</th><th>Storm</th><th>Period</th><th>Change</th><th>Surcharge</th><th>Flood</th><th>Overflow</th><th>Act.</th><th>Level</th></tr><tr><td>1.000</td><td>1</td><td>240</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>63.117</td></tr><tr><td>1.001</td><td>2</td><td>240</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>63.117</td></tr><tr><td>1.002</td><td>3 HB</td><td>240</td><td>Summer</td><td>2</td><td>+0%</td><td>2/15</td><td>Summer</td><td></td><td>63.116</td></tr><tr><td>1.003</td><td>4</td><td>120</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.684</td></tr><tr><td>1.004</td><td>5</td><td>60</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.547</td></tr><tr><td>1.005</td><td>6</td><td>60</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.451</td></tr><tr><td>1.006</td><td>7</td><td>60</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.349</td></tr><tr><td>2.000</td><td>8</td><td>15</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.686</td></tr><tr><td>2.001</td><td>9</td><td>480</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.618</td></tr><tr><td>2.002</td><td>10 HB</td><td>480</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.617</td></tr><tr><td>2.003</td><td>11</td><td>360</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.256</td></tr><tr><td>2.004</td><td>12</td><td>360</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.194</td></tr><tr><td>2.005</td><td>13</td><td>360</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.181</td></tr><tr><td>1.007</td><td>14</td><td>360</td><td>Summer</td><td>2</td><td>+0%</td><td></td><td></td><td></td><td>62.174</td></tr></table>									US/MH		Return Climate		First (X)	First (Y)	First (Z)	Overflow	Water	PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level	1.000	1	240	Summer	2	+0%				63.117	1.001	2	240	Summer	2	+0%				63.117	1.002	3 HB	240	Summer	2	+0%	2/15	Summer		63.116	1.003	4	120	Summer	2	+0%				62.684	1.004	5	60	Summer	2	+0%				62.547	1.005	6	60	Summer	2	+0%				62.451	1.006	7	60	Summer	2	+0%				62.349	2.000	8	15	Summer	2	+0%				62.686	2.001	9	480	Summer	2	+0%				62.618	2.002	10 HB	480	Summer	2	+0%				62.617	2.003	11	360	Summer	2	+0%				62.256	2.004	12	360	Summer	2	+0%				62.194	2.005	13	360	Summer	2	+0%				62.181	1.007	14	360	Summer	2	+0%				62.174
US/MH		Return Climate		First (X)	First (Y)	First (Z)	Overflow	Water																																																																																																																																																															
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level																																																																																																																																																														
1.000	1	240	Summer	2	+0%				63.117																																																																																																																																																														
1.001	2	240	Summer	2	+0%				63.117																																																																																																																																																														
1.002	3 HB	240	Summer	2	+0%	2/15	Summer		63.116																																																																																																																																																														
1.003	4	120	Summer	2	+0%				62.684																																																																																																																																																														
1.004	5	60	Summer	2	+0%				62.547																																																																																																																																																														
1.005	6	60	Summer	2	+0%				62.451																																																																																																																																																														
1.006	7	60	Summer	2	+0%				62.349																																																																																																																																																														
2.000	8	15	Summer	2	+0%				62.686																																																																																																																																																														
2.001	9	480	Summer	2	+0%				62.618																																																																																																																																																														
2.002	10 HB	480	Summer	2	+0%				62.617																																																																																																																																																														
2.003	11	360	Summer	2	+0%				62.256																																																																																																																																																														
2.004	12	360	Summer	2	+0%				62.194																																																																																																																																																														
2.005	13	360	Summer	2	+0%				62.181																																																																																																																																																														
1.007	14	360	Summer	2	+0%				62.174																																																																																																																																																														
©1982-2020 Innovyze																																																																																																																																																																							

Coast Consulting Engineers Ltd		Page 11
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:2	
Date 09/06/2023 File 230609 REVISED SURFACE W...	Designed by RH Checked by PL	
Innovyze	Network 2020.1	

Summary of Critical Results by Maximum Level (Rank 1) for 180518 SW1.SWS


PN	US/MH Name	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Half Drain	Pipe	Status	Level
		Depth (m)	Volume (m³)			Time (mins)	Flow (l/s)		Exceeded
1.000	1	-0.871	0.000	0.00		80	4.4		OK
1.001	2	-0.766	0.000	0.01		83	6.1		OK
1.002	3 HB	0.117	0.000	0.16			6.0	SURCHARGED	
1.003	4	-0.130	0.000	0.37		140	13.7		OK
1.004	5	-0.117	0.000	0.46			16.5		OK
1.005	6	-0.109	0.000	0.52			18.8		OK
1.006	7	-0.099	0.000	0.60		51	20.8		OK
2.000	8	-0.425	0.000	0.08		6	19.1		OK
2.001	9	-0.272	0.000	0.07		102	15.9		OK
2.002	10 HB	-0.007	0.000	0.06		192	5.8		OK
2.003	11	-0.300	0.000	0.08		315	7.8		OK
2.004	12	-0.260	0.000	0.11		248	9.5		OK
2.005	13	-0.231	0.000	0.13			10.8		OK
1.007	14	-0.194	0.000	0.29			27.8		OK

Coast Consulting Engineers Ltd		Page 12
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:2	
Date 09/06/2023 File 230609 REVISED SURFACE W...	Designed by RH Checked by PL	
Innovyze	Network 2020.1	

Summary of Critical Results by Maximum Level (Rank 1) for 180518 SW1.SWS
















US/MH		Return Climate		First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act. Level
								(m)
1.008	15	360 Summer	2	+0%				62.152
3.000	16	360 Summer	2	+0%				62.138
1.009	17 HB	360 Summer	2	+0%				62.137
1.010	18	360 Summer	2	+0%				61.897

US/MH		Surcharged	Flooded	Half Drain		Pipe	Level	
PN	Name	Depth (m)	Volume (m ³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	Status Exceeded
1.008	15	-0.142	0.000	0.29		126	27.7	OK
3.000	16	-0.137	0.000	0.02		115	2.0	OK
1.009	17 HB	-0.015	0.000	0.40		154	25.4	OK
1.010	18	-0.146	0.000	0.52			25.4	OK

Coast Consulting Engineers Ltd		Page 0
Suite 6, Vita House	FLOSH MEADOWS	
Fish Quay	CLEATOR	
North Shields NE30 1JA	1:30	
Date 09/06/2023	Designed by RH	
File 230609 REVISED SURFACE W...	Checked by PL	
Innovyze	Network 2020.1	

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for 180518 SW1.SWS

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	41.957	0.105	399.6	0.061	5.00	0.0	0.600	o	975	Pipe/Conduit	
1.001	53.639	0.134	400.3	0.118	0.00	0.0	0.600	o	975	Pipe/Conduit	
1.002	31.512	0.185	170.3	0.129	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.003	25.483	0.150	169.9	0.104	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.004	17.652	0.104	169.7	0.035	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.005	18.982	0.112	169.5	0.028	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.006	13.655	0.080	170.7	0.029	0.00	0.0	0.600	o	225	Pipe/Conduit	
2.000	71.706	0.221	324.5	0.115	5.00	0.0	0.600	o	525	Pipe/Conduit	
2.001	37.730	0.116	325.3	0.225	0.00	0.0	0.600	o	525	Pipe/Conduit	
2.002	22.253	0.068	325.0	0.065	0.00	0.0	0.600	o	375	Pipe/Conduit	
2.003	33.218	0.102	325.7	0.065	0.00	0.0	0.600	o	375	Pipe/Conduit	
2.004	13.246	0.041	323.1	0.062	0.00	0.0	0.600	o	375	Pipe/Conduit	
2.005	14.105	0.043	328.0	0.042	0.00	0.0	0.600	o	375	Pipe/Conduit	
1.007	24.092	0.074	325.6	0.021	0.00	0.0	0.600	o	375	Pipe/Conduit	
1.008	21.726	0.067	324.3	0.029	0.00	0.0	0.600	o	375	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	0.00	5.43	63.013	0.061	0.0	0.0	0.0	1.64	1225.0	0.0
1.001	0.00	5.97	62.908	0.179	0.0	0.0	0.0	1.64	1223.9	0.0
1.002	0.00	6.50	62.774	0.308	0.0	0.0	0.0	1.00	39.7	0.0
1.003	0.00	6.92	62.589	0.412	0.0	0.0	0.0	1.00	39.8	0.0
1.004	0.00	7.22	62.439	0.447	0.0	0.0	0.0	1.00	39.8	0.0
1.005	0.00	7.53	62.335	0.475	0.0	0.0	0.0	1.00	39.8	0.0
1.006	0.00	7.76	62.223	0.504	0.0	0.0	0.0	1.00	39.7	0.0
2.000	0.00	5.97	62.586	0.115	0.0	0.0	0.0	1.24	268.0	0.0
2.001	0.00	6.47	62.365	0.340	0.0	0.0	0.0	1.24	267.7	0.0
2.002	0.00	6.85	62.249	0.405	0.0	0.0	0.0	1.00	110.4	0.0
2.003	0.00	7.40	62.181	0.470	0.0	0.0	0.0	1.00	110.3	0.0
2.004	0.00	7.62	62.079	0.532	0.0	0.0	0.0	1.00	110.7	0.0
2.005	0.00	7.86	62.038	0.574	0.0	0.0	0.0	0.99	109.9	0.0
1.007	0.00	8.26	61.993	1.099	0.0	0.0	0.0	1.00	110.3	0.0
1.008	0.00	8.62	61.919	1.128	0.0	0.0	0.0	1.00	110.5	0.0

Coast Consulting Engineers Ltd

Page 1

Suite 6, Vita House
Fish Quay
North Shields NE30 1JA

FLOSH MEADOWS
CLEATOR
1:30

Date 09/06/2023
File 230609 REVISED SURFACE W...




Designed by RH
Checked by PL

Innovyze

Network 2020.1

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for 180518 SW1.SWS

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
3.000	15.459	0.048	322.1	0.070	5.00	0.0	0.600	o	375	Pipe/Conduit	
1.009	26.775	0.109	245.6	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
1.010	3.900	0.016	243.8	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
3.000	0.00	5.26	61.900	0.070	0.0	0.0	0.0	1.00	110.9	0.0
1.009	0.00	9.07	61.852	1.198	0.0	0.0	0.0	1.00	70.6	0.0
1.010	0.00	9.13	61.743	1.198	0.0	0.0	0.0	1.00	70.9	0.0

Free Flowing Outfall Details for 180518 SW1.SWS

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.010	C1	63.006	61.727	61.727	1350	0

Simulation Criteria for 180518 SW1.SWS

Volumetric Runoff Coeff 0.750

Additional Flow - % of Total Flow 0.000

Areal Reduction Factor 1.000

MADD Factor * 10m³/ha Storage 2.000

Hot Start (mins) 0

Inlet Coefficient 0.800

Hot Start Level (mm) 0

Flow per Person per Day (l/per/day) 0.000

Manhole Headloss Coeff (Global) 0.500

Run Time (mins) 60

Foul Sewage per hectare (l/s) 0.000

Output Interval (mins) 1

Number of Input Hydrographs 0

Number of Storage Structures 13

Number of Online Controls 3

Number of Time/Area Diagrams 0

Number of Offline Controls 0

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model

FSR

M5-60 (mm) 19.600


Return Period (years) 2


Ratio R 0.223


Region England and Wales


Profile Type Summer


©1982-2020 Innovyze


Coast Consulting Engineers Ltd		Page 2
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:30	
Date 09/06/2023	Designed by RH	
File 230609 REVISED SURFACE W...	Checked by PL	
Innovyze	Network 2020.1	
<div>Synthetic Rainfall Details</div> <div>Cv (Summer) 0.750 Storm Duration (mins) 30 Cv (Winter) 0.840</div>		
©1982-2020 Innovyze		


Coast Consulting Engineers Ltd			Page 3																																																																									
Suite 6, Vita House Fish Quay North Shields NE30 1JA		FLOSH MEADOWS CLEATOR 1:30																																																																										
Date 09/06/2023		Designed by RH																																																																										
File 230609 REVISED SURFACE W...		Checked by PL																																																																										
Innovyze		Network 2020.1																																																																										
Online Controls for 180518 SW1.SWS																																																																												
Hydro-Brake® Optimum Manhole: 3 HB, DS/PN: 1.002, Volume (m³): 45.9																																																																												
Unit Reference MD-SHE-0107-7000-2119-7000																																																																												
Design Head (m) 2.119																																																																												
Design Flow (l/s) 7.0																																																																												
Flush-Flo™ Calculated																																																																												
Objective Minimise upstream storage																																																																												
Application Surface																																																																												
Sump Available Yes																																																																												
Diameter (mm) 107																																																																												
Invert Level (m) 62.774																																																																												
Minimum Outlet Pipe Diameter (mm) 150																																																																												
Suggested Manhole Diameter (mm) 1200																																																																												
<table><tr><td>Control Points</td><td>Head (m)</td><td>Flow (l/s)</td><td>Control Points</td><td>Head (m)</td><td>Flow (l/s)</td></tr><tr><td>Design Point (Calculated)</td><td>2.119</td><td>7.0</td><td>Kick-Flo®</td><td>0.957</td><td>4.8</td></tr><tr><td>Flush-Flo™</td><td>0.469</td><td>6.1</td><td>Mean Flow over Head Range</td><td>-</td><td>5.6</td></tr></table>					Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)	Design Point (Calculated)	2.119	7.0	Kick-Flo®	0.957	4.8	Flush-Flo™	0.469	6.1	Mean Flow over Head Range	-	5.6																																																						
Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)																																																																							
Design Point (Calculated)	2.119	7.0	Kick-Flo®	0.957	4.8																																																																							
Flush-Flo™	0.469	6.1	Mean Flow over Head Range	-	5.6																																																																							
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated																																																																												
<table><tr><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td></tr><tr><td>0.100</td><td>3.7</td><td>1.200</td><td>5.4</td><td>3.000</td><td>8.2</td><td>7.000</td><td>12.3</td></tr><tr><td>0.200</td><td>5.4</td><td>1.400</td><td>5.8</td><td>3.500</td><td>8.9</td><td>7.500</td><td>12.7</td></tr><tr><td>0.300</td><td>5.9</td><td>1.600</td><td>6.1</td><td>4.000</td><td>9.4</td><td>8.000</td><td>13.1</td></tr><tr><td>0.400</td><td>6.0</td><td>1.800</td><td>6.5</td><td>4.500</td><td>10.0</td><td>8.500</td><td>13.5</td></tr><tr><td>0.500</td><td>6.1</td><td>2.000</td><td>6.8</td><td>5.000</td><td>10.5</td><td>9.000</td><td>13.9</td></tr><tr><td>0.600</td><td>6.0</td><td>2.200</td><td>7.1</td><td>5.500</td><td>11.0</td><td>9.500</td><td>14.3</td></tr><tr><td>0.800</td><td>5.6</td><td>2.400</td><td>7.4</td><td>6.000</td><td>11.4</td><td></td><td></td></tr><tr><td>1.000</td><td>4.9</td><td>2.600</td><td>7.7</td><td>6.500</td><td>11.9</td><td></td><td></td></tr></table>					Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	0.100	3.7	1.200	5.4	3.000	8.2	7.000	12.3	0.200	5.4	1.400	5.8	3.500	8.9	7.500	12.7	0.300	5.9	1.600	6.1	4.000	9.4	8.000	13.1	0.400	6.0	1.800	6.5	4.500	10.0	8.500	13.5	0.500	6.1	2.000	6.8	5.000	10.5	9.000	13.9	0.600	6.0	2.200	7.1	5.500	11.0	9.500	14.3	0.800	5.6	2.400	7.4	6.000	11.4			1.000	4.9	2.600	7.7	6.500	11.9		
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)																																																																					
0.100	3.7	1.200	5.4	3.000	8.2	7.000	12.3																																																																					
0.200	5.4	1.400	5.8	3.500	8.9	7.500	12.7																																																																					
0.300	5.9	1.600	6.1	4.000	9.4	8.000	13.1																																																																					
0.400	6.0	1.800	6.5	4.500	10.0	8.500	13.5																																																																					
0.500	6.1	2.000	6.8	5.000	10.5	9.000	13.9																																																																					
0.600	6.0	2.200	7.1	5.500	11.0	9.500	14.3																																																																					
0.800	5.6	2.400	7.4	6.000	11.4																																																																							
1.000	4.9	2.600	7.7	6.500	11.9																																																																							
Hydro-Brake® Optimum Manhole: 10 HB, DS/PN: 2.002, Volume (m³): 13.2																																																																												
Unit Reference MD-SHE-0107-6000-1575-6000																																																																												
Design Head (m) 1.575																																																																												
Design Flow (l/s) 6.0																																																																												
Flush-Flo™ Calculated																																																																												
Objective Minimise upstream storage																																																																												
Application Surface																																																																												
Sump Available Yes																																																																												
Diameter (mm) 106																																																																												
Invert Level (m) 62.249																																																																												
Minimum Outlet Pipe Diameter (mm) 150																																																																												
©1982-2020 Innovyze																																																																												


Coast Consulting Engineers Ltd				Page 4			
Suite 6, Vita House		FLOSH MEADOWS					
Fish Quay		CLEATOR					
North Shields NE30 1JA		1:30					
Date 09/06/2023		Designed by RH					
File 230609 REVISED SURFACE W...		Checked by PL					
Innovyze		Network 2020.1					
<hr/>							
Hydro-Brake® Optimum Manhole: 10 HB, DS/PN: 2.002, Volume (m³): 13.2							
Suggested Manhole Diameter (mm) 1200							
Control Points		Head (m)	Flow (l/s)	Control Points		Head (m)	Flow (l/s)
Design Point (Calculated)		1.575	6.0	Kick-Flo®		0.952	4.7
Flush-Flo™		0.468	5.9	Mean Flow over Head Range		-	5.2
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated							
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.6	1.200	5.3	3.000	8.1	7.000	12.1
0.200	5.3	1.400	5.7	3.500	8.7	7.500	12.5
0.300	5.7	1.600	6.0	4.000	9.3	8.000	12.9
0.400	5.9	1.800	6.4	4.500	9.8	8.500	13.3
0.500	5.9	2.000	6.7	5.000	10.3	9.000	13.7
0.600	5.9	2.200	7.0	5.500	10.8	9.500	14.0
0.800	5.5	2.400	7.3	6.000	11.3		
1.000	4.9	2.600	7.6	6.500	11.7		
<hr/>							
Hydro-Brake® Optimum Manhole: 17 HB, DS/PN: 1.009, Volume (m³): 9.6							
Unit Reference MD-SHE-0235-3200-1642-3200							
Design Head (m)				1.642			
Design Flow (l/s)				32.0			
Flush-Flo™				Calculated			
Objective				Minimise upstream storage			
Application				Surface			
Sump Available				Yes			
Diameter (mm)				235			
Invert Level (m)				61.852			
Minimum Outlet Pipe Diameter (mm)				300			
Suggested Manhole Diameter (mm)				1800			
Control Points		Head (m)	Flow (l/s)	Control Points		Head (m)	Flow (l/s)
Design Point (Calculated)		1.642	32.0	Kick-Flo®		1.101	26.4
Flush-Flo™		0.503	32.0	Mean Flow over Head Range		-	27.5
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated							
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	7.8	0.200	23.7	0.300	30.6	0.400	31.7
<hr/>							
©1982-2020 Innovyze							


Coast Consulting Engineers Ltd		Page 6																																																																								
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:30																																																																									
Date 09/06/2023	Designed by RH																																																																									
File 230609 REVISED SURFACE W...	Checked by PL																																																																									
Innovyze	Network 2020.1																																																																									
<div>Storage Structures for 180518 SW1.SWS</div> <div>Cellular Storage Manhole: 1, DS/PN: 1.000</div> <div>Invert Level (m) 63.585 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>51.8</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>51.8</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table> <div>Cellular Storage Manhole: 2, DS/PN: 1.001</div> <div>Invert Level (m) 63.015 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>220.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>220.0</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table> <div>Cellular Storage Manhole: 4, DS/PN: 1.003</div> <div>Invert Level (m) 62.589 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>129.5</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>129.5</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table> <div>Cellular Storage Manhole: 6, DS/PN: 1.005</div> <div>Invert Level (m) 62.335 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>25.9</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>25.9</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table>			Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	51.8	0.0	0.521	0.0	0.0	0.520	51.8	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	220.0	0.0	0.521	0.0	0.0	0.520	220.0	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	129.5	0.0	0.521	0.0	0.0	0.520	129.5	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	25.9	0.0	0.521	0.0	0.0	0.520	25.9	0.0			
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																					
0.000	51.8	0.0	0.521	0.0	0.0																																																																					
0.520	51.8	0.0																																																																								
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																					
0.000	220.0	0.0	0.521	0.0	0.0																																																																					
0.520	220.0	0.0																																																																								
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																					
0.000	129.5	0.0	0.521	0.0	0.0																																																																					
0.520	129.5	0.0																																																																								
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																					
0.000	25.9	0.0	0.521	0.0	0.0																																																																					
0.520	25.9	0.0																																																																								
©1982-2020 Innovyze																																																																										

Coast Consulting Engineers Ltd			Page 7																																																																										
Suite 6, Vita House		FLOSH MEADOWS																																																																											
Fish Quay		CLEATOR																																																																											
North Shields NE30 1JA		1:30																																																																											
Date 09/06/2023		Designed by RH																																																																											
File 230609 REVISED SURFACE W...		Checked by PL																																																																											
Innovyze			Network 2020.1																																																																										
<p style="text-align: center;"><u>Cellular Storage Manhole: 7, DS/PN: 1.006</u></p> <p style="text-align: center;">Invert Level (m) 62.224 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>25.9</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>25.9</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 8, DS/PN: 2.000</u></p> <p style="text-align: center;">Invert Level (m) 63.413 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>77.7</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>77.7</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 9, DS/PN: 2.001</u></p> <p style="text-align: center;">Invert Level (m) 62.621 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>388.5</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>388.5</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 10 HB, DS/PN: 2.002</u></p> <p style="text-align: center;">Invert Level (m) 62.249 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>170.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>170.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 11, DS/PN: 2.003</u></p> <p style="text-align: center;">Invert Level (m) 62.181 Infiltration Coefficient Side (m/hr) 0.00000 Infiltration Coefficient Base (m/hr) 0.00000 Safety Factor 2.0</p>						Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	25.9	0.0	0.521	0.0	0.0	0.520	25.9	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	77.7	0.0	0.521	0.0	0.0	0.520	77.7	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	388.5	0.0	0.521	0.0	0.0	0.520	388.5	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	170.0	0.0	0.521	0.0	0.0	0.520	170.0	0.0			
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	25.9	0.0	0.521	0.0	0.0																																																																								
0.520	25.9	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	77.7	0.0	0.521	0.0	0.0																																																																								
0.520	77.7	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	388.5	0.0	0.521	0.0	0.0																																																																								
0.520	388.5	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	170.0	0.0	0.521	0.0	0.0																																																																								
0.520	170.0	0.0																																																																											
©1982-2020 Innovyze																																																																													

Coast Consulting Engineers Ltd			Page 8																																																																										
Suite 6, Vita House Fish Quay North Shields NE30 1JA		FLOSH MEADOWS CLEATOR 1:30																																																																											
Date 09/06/2023		Designed by RH																																																																											
File 230609 REVISED SURFACE W...		Checked by PL																																																																											
Innovyze			Network 2020.1																																																																										
<p style="text-align: center;"><u>Cellular Storage Manhole: 11, DS/PN: 2.003</u></p> <p style="text-align: center;">Porosity 0.95</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>200.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>200.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 12, DS/PN: 2.004</u></p> <p style="text-align: center;">Invert Level (m) 62.079 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>129.5</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>129.5</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 15, DS/PN: 1.008</u></p> <p style="text-align: center;">Invert Level (m) 61.919 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>30.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>30.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 16, DS/PN: 3.000</u></p> <p style="text-align: center;">Invert Level (m) 61.900 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>51.8</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>51.8</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 17 HB, DS/PN: 1.009</u></p> <p style="text-align: center;">Invert Level (m) 61.852 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p>						Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	200.0	0.0	0.521	0.0	0.0	0.520	200.0	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	129.5	0.0	0.521	0.0	0.0	0.520	129.5	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	30.0	0.0	0.521	0.0	0.0	0.520	30.0	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	51.8	0.0	0.521	0.0	0.0	0.520	51.8	0.0			
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	200.0	0.0	0.521	0.0	0.0																																																																								
0.520	200.0	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	129.5	0.0	0.521	0.0	0.0																																																																								
0.520	129.5	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	30.0	0.0	0.521	0.0	0.0																																																																								
0.520	30.0	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	51.8	0.0	0.521	0.0	0.0																																																																								
0.520	51.8	0.0																																																																											
©1982-2020 Innovyze																																																																													


Coast Consulting Engineers Ltd			Page 9																				
Suite 6, Vita House		FLOSH MEADOWS																					
Fish Quay		CLEATOR																					
North Shields NE30 1JA		1:30																					
Date 09/06/2023		Designed by RH																					
File 230609 REVISED SURFACE W...		Checked by PL																					
Innovyze			Network 2020.1																				
<div>Cellular Storage Manhole: 17 HB, DS/PN: 1.009</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>77.7</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>77.7</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table>						Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	77.7	0.0	0.521	0.0	0.0	0.520	77.7	0.0			
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																		
0.000	77.7	0.0	0.521	0.0	0.0																		
0.520	77.7	0.0																					
©1982-2020 Innovyze																							

Coast Consulting Engineers Ltd										Page 10																																																																																																																																																							
Suite 6, Vita House Fish Quay North Shields NE30 1JA					FLOSH MEADOWS CLEATOR 1:30																																																																																																																																																												
Date 09/06/2023					Designed by RH																																																																																																																																																												
File 230609 REVISED SURFACE W...					Checked by PL																																																																																																																																																												
Innovyze					Network 2020.1																																																																																																																																																												
<u>Summary of Critical Results by Maximum Level (Rank 1) for 180518 SW1.SWS</u>																																																																																																																																																																	
<u>Simulation Criteria</u>																																																																																																																																																																	
Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000																																																																																																																																																																	
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000																																																																																																																																																																	
Hot Start Level (mm) 0 Inlet Coefficient 0.800																																																																																																																																																																	
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000																																																																																																																																																																	
Foul Sewage per hectare (l/s) 0.000																																																																																																																																																																	
Number of Input Hydrographs 0 Number of Storage Structures 13																																																																																																																																																																	
Number of Online Controls 3 Number of Time/Area Diagrams 0																																																																																																																																																																	
Number of Offline Controls 0 Number of Real Time Controls 0																																																																																																																																																																	
<u>Synthetic Rainfall Details</u>																																																																																																																																																																	
Rainfall Model FSR Ratio R 0.220																																																																																																																																																																	
Region England and Wales Cv (Summer) 1.000																																																																																																																																																																	
M5-60 (mm) 18.600 Cv (Winter) 1.000																																																																																																																																																																	
Margin for Flood Risk Warning (mm) 300.0																																																																																																																																																																	
Analysis Timestep 2.5 Second Increment (Extended)																																																																																																																																																																	
DTS Status OFF																																																																																																																																																																	
DVD Status OFF																																																																																																																																																																	
Inertia Status OFF																																																																																																																																																																	
Profile(s) Summer and Winter																																																																																																																																																																	
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440																																																																																																																																																																	
Return Period(s) (years) 30																																																																																																																																																																	
Climate Change (%) 0																																																																																																																																																																	
<table><tr><th>PN</th><th>US/MH Name</th><th>Storm</th><th>Return Period</th><th>Climate Change</th><th>First (X) Surchage</th><th>First (Y) Flood</th><th>First (Z) Overflow</th><th>Overflow Act.</th><th>Water Level (m)</th></tr><tr><td>1.000</td><td>1</td><td>360 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>63.286</td></tr><tr><td>1.001</td><td>2</td><td>360 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>63.286</td></tr><tr><td>1.002</td><td>3 HB</td><td>360 Summer</td><td>30</td><td>+0%</td><td>30/15 Summer</td><td></td><td></td><td></td><td>63.286</td></tr><tr><td>1.003</td><td>4</td><td>60 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.721</td></tr><tr><td>1.004</td><td>5</td><td>60 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.600</td></tr><tr><td>1.005</td><td>6</td><td>60 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.524</td></tr><tr><td>1.006</td><td>7</td><td>60 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.437</td></tr><tr><td>2.000</td><td>8</td><td>600 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.751</td></tr><tr><td>2.001</td><td>9</td><td>600 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.751</td></tr><tr><td>2.002</td><td>10 HB</td><td>600 Summer</td><td>30</td><td>+0%</td><td>30/30 Summer</td><td></td><td></td><td></td><td>62.750</td></tr><tr><td>2.003</td><td>11</td><td>240 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.328</td></tr><tr><td>2.004</td><td>12</td><td>240 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.323</td></tr><tr><td>2.005</td><td>13</td><td>240 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.318</td></tr><tr><td>1.007</td><td>14</td><td>240 Summer</td><td>30</td><td>+0%</td><td></td><td></td><td></td><td></td><td>62.313</td></tr></table>												PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	1.000	1	360 Summer	30	+0%					63.286	1.001	2	360 Summer	30	+0%					63.286	1.002	3 HB	360 Summer	30	+0%	30/15 Summer				63.286	1.003	4	60 Summer	30	+0%					62.721	1.004	5	60 Summer	30	+0%					62.600	1.005	6	60 Summer	30	+0%					62.524	1.006	7	60 Summer	30	+0%					62.437	2.000	8	600 Summer	30	+0%					62.751	2.001	9	600 Summer	30	+0%					62.751	2.002	10 HB	600 Summer	30	+0%	30/30 Summer				62.750	2.003	11	240 Summer	30	+0%					62.328	2.004	12	240 Summer	30	+0%					62.323	2.005	13	240 Summer	30	+0%					62.318	1.007	14	240 Summer	30	+0%					62.313
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)																																																																																																																																																								
1.000	1	360 Summer	30	+0%					63.286																																																																																																																																																								
1.001	2	360 Summer	30	+0%					63.286																																																																																																																																																								
1.002	3 HB	360 Summer	30	+0%	30/15 Summer				63.286																																																																																																																																																								
1.003	4	60 Summer	30	+0%					62.721																																																																																																																																																								
1.004	5	60 Summer	30	+0%					62.600																																																																																																																																																								
1.005	6	60 Summer	30	+0%					62.524																																																																																																																																																								
1.006	7	60 Summer	30	+0%					62.437																																																																																																																																																								
2.000	8	600 Summer	30	+0%					62.751																																																																																																																																																								
2.001	9	600 Summer	30	+0%					62.751																																																																																																																																																								
2.002	10 HB	600 Summer	30	+0%	30/30 Summer				62.750																																																																																																																																																								
2.003	11	240 Summer	30	+0%					62.328																																																																																																																																																								
2.004	12	240 Summer	30	+0%					62.323																																																																																																																																																								
2.005	13	240 Summer	30	+0%					62.318																																																																																																																																																								
1.007	14	240 Summer	30	+0%					62.313																																																																																																																																																								
©1982-2020 Innovyze																																																																																																																																																																	

Coast Consulting Engineers Ltd		Page 11
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:30	
Date 09/06/2023 File 230609 REVISED SURFACE W...	Designed by RH Checked by PL	
Innovyze	Network 2020.1	

Summary of Critical Results by Maximum Level (Rank 1) for 180518 SW1.SWS


PN	US/MH Name	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Half Drain	Pipe	Status	Level
		Depth (m)	Volume (m³)			Time (mins)	Flow (l/s)		Exceeded
1.000	1	-0.702	0.000	0.01		183	6.1		OK
1.001	2	-0.597	0.000	0.01		181	5.2		OK
1.002	3 HB	0.287	0.000	0.16			6.1	SURCHARGED	
1.003	4	-0.093	0.000	0.65		41	23.7		OK
1.004	5	-0.064	0.000	0.85			30.4		OK
1.005	6	-0.036	0.000	0.93		20	33.4		OK
1.006	7	-0.011	0.000	1.00		18	34.5		OK
2.000	8	-0.360	0.000	0.03		250	8.6		OK
2.001	9	-0.139	0.000	0.08		233	18.9		OK
2.002	10 HB	0.126	0.000	0.06		405	5.9	SURCHARGED	
2.003	11	-0.227	0.000	0.10		101	9.9		OK
2.004	12	-0.131	0.000	0.17		96	14.0		OK
2.005	13	-0.094	0.000	0.18			14.7		OK
1.007	14	-0.055	0.000	0.41			39.2		OK

Coast Consulting Engineers Ltd		Page 12
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:30	
Date 09/06/2023 File 230609 REVISED SURFACE W...	Designed by RH Checked by PL	
Innovyze	Network 2020.1	

Summary of Critical Results by Maximum Level (Rank 1) for 180518 SW1.SWS
















										Water
US/MH			Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Level	
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	(m)	
1.008	15	240 Summer	30	+0%	30/240 Summer				62.296	
3.000	16	240 Summer	30	+0%	30/240 Summer				62.280	
1.009	17 HB	240 Summer	30	+0%	30/60 Summer				62.278	
1.010	18	240 Summer	30	+0%					61.916	

US/MH		Surcharged	Flooded	Half Drain		Pipe	Level		
PN	Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	Status	Exceeded
1.008	15	0.002	0.000	0.40		122	37.5	SURCHARGED	
3.000	16	0.005	0.000	0.03		126	2.9	SURCHARGED	
1.009	17 HB	0.126	0.000	0.48		135	30.8	SURCHARGED	
1.010	18	-0.127	0.000	0.63			30.8	OK	

Coast Consulting Engineers Ltd		Page 0
Suite 6, Vita House	FLOSH MEADOWS	
Fish Quay	CLEATOR	
North Shields NE30 1JA	1:100 +50%	
Date 09/06/2023	Designed by RH	
File 230609 REVISED SURFACE W...	Checked by PL	
Innovyze	Network 2020.1	


STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for 180518 SW1.SWS

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	41.957	0.105	399.6	0.061	5.00	0.0	0.600	o	975	Pipe/Conduit	
1.001	53.639	0.134	400.3	0.118	0.00	0.0	0.600	o	975	Pipe/Conduit	
1.002	31.512	0.185	170.3	0.129	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.003	25.483	0.150	169.9	0.104	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.004	17.652	0.104	169.7	0.035	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.005	18.982	0.112	169.5	0.028	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.006	13.655	0.080	170.7	0.029	0.00	0.0	0.600	o	225	Pipe/Conduit	
2.000	71.706	0.221	324.5	0.115	5.00	0.0	0.600	o	525	Pipe/Conduit	
2.001	37.730	0.116	325.3	0.225	0.00	0.0	0.600	o	525	Pipe/Conduit	
2.002	22.253	0.068	325.0	0.065	0.00	0.0	0.600	o	375	Pipe/Conduit	
2.003	33.218	0.102	325.7	0.065	0.00	0.0	0.600	o	375	Pipe/Conduit	
2.004	13.246	0.041	323.1	0.062	0.00	0.0	0.600	o	375	Pipe/Conduit	
2.005	14.105	0.043	328.0	0.042	0.00	0.0	0.600	o	375	Pipe/Conduit	
1.007	24.092	0.074	325.6	0.021	0.00	0.0	0.600	o	375	Pipe/Conduit	
1.008	21.726	0.067	324.3	0.029	0.00	0.0	0.600	o	375	Pipe/Conduit	




Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	0.00	5.43	63.013	0.061	0.0	0.0	0.0	1.64	1225.0	0.0
1.001	0.00	5.97	62.908	0.179	0.0	0.0	0.0	1.64	1223.9	0.0
1.002	0.00	6.50	62.774	0.308	0.0	0.0	0.0	1.00	39.7	0.0
1.003	0.00	6.92	62.589	0.412	0.0	0.0	0.0	1.00	39.8	0.0
1.004	0.00	7.22	62.439	0.447	0.0	0.0	0.0	1.00	39.8	0.0
1.005	0.00	7.53	62.335	0.475	0.0	0.0	0.0	1.00	39.8	0.0
1.006	0.00	7.76	62.223	0.504	0.0	0.0	0.0	1.00	39.7	0.0
2.000	0.00	5.97	62.586	0.115	0.0	0.0	0.0	1.24	268.0	0.0
2.001	0.00	6.47	62.365	0.340	0.0	0.0	0.0	1.24	267.7	0.0
2.002	0.00	6.85	62.249	0.405	0.0	0.0	0.0	1.00	110.4	0.0
2.003	0.00	7.40	62.181	0.470	0.0	0.0	0.0	1.00	110.3	0.0
2.004	0.00	7.62	62.079	0.532	0.0	0.0	0.0	1.00	110.7	0.0
2.005	0.00	7.86	62.038	0.574	0.0	0.0	0.0	0.99	109.9	0.0
1.007	0.00	8.26	61.993	1.099	0.0	0.0	0.0	1.00	110.3	0.0
1.008	0.00	8.62	61.919	1.128	0.0	0.0	0.0	1.00	110.5	0.0

Coast Consulting Engineers Ltd										Page 1	
Suite 6, Vita House Fish Quay North Shields NE30 1JA					FLOSH MEADOWS CLEATOR 1:100 +50%						
Date 09/06/2023					Designed by RH						
File 230609 REVISED SURFACE W...					Checked by PL						
Innovyze					Network 2020.1						

STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for 180518 SW1.SWS

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
3.000	15.459	0.048	322.1	0.070	5.00	0.0	0.600	o	375	Pipe/Conduit	
1.009	26.775	0.109	245.6	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
1.010	3.900	0.016	243.8	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
3.000	0.00	5.26	61.900	0.070	0.0	0.0	0.0	1.00	110.9	0.0
1.009	0.00	9.07	61.852	1.198	0.0	0.0	0.0	1.00	70.6	0.0
1.010	0.00	9.13	61.743	1.198	0.0	0.0	0.0	1.00	70.9	0.0

Free Flowing Outfall Details for 180518 SW1.SWS

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D, L (mm)	W (mm)
1.010	C1	63.006	61.727	61.727	1350	0

Simulation Criteria for 180518 SW1.SWS


Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1


Number of Input Hydrographs	0	Number of Storage Structures	13
Number of Online Controls	3	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0


Synthetic Rainfall Details


Rainfall Model	FSR	M5-60 (mm)	19.600
Return Period (years)	2	Ratio R	0.223
Region England and Wales		Profile Type	Summer


©1982-2020 Innovyze


Coast Consulting Engineers Ltd		Page 2
Suite 6, Vita House	FLOSH MEADOWS	
Fish Quay	CLEATOR	
North Shields NE30 1JA	1:100 +50%	
Date 09/06/2023	Designed by RH	
File 230609 REVISED SURFACE W...	Checked by PL	
Innovyze	Network 2020.1	
<p style="text-align: center;"><u>Synthetic Rainfall Details</u></p> <p style="text-align: center;">Cv (Summer) 0.750 Storm Duration (mins) 30 Cv (Winter) 0.840</p>		
<p style="text-align: center;">©1982-2020 Innovyze</p>		


Coast Consulting Engineers Ltd			Page 3																																																																									
Suite 6, Vita House		FLOSH MEADOWS																																																																										
Fish Quay		CLEATOR																																																																										
North Shields NE30 1JA		1:100 +50%																																																																										
Date 09/06/2023		Designed by RH																																																																										
File 230609 REVISED SURFACE W...		Checked by PL																																																																										
Innovyze		Network 2020.1																																																																										
Online Controls for 180518 SW1.SWS																																																																												
Hydro-Brake® Optimum Manhole: 3 HB, DS/PN: 1.002, Volume (m³): 45.9																																																																												
Unit Reference MD-SHE-0107-7000-2119-7000																																																																												
Design Head (m) 2.119																																																																												
Design Flow (l/s) 7.0																																																																												
Flush-Flo™ Calculated																																																																												
Objective Minimise upstream storage																																																																												
Application Surface																																																																												
Sump Available Yes																																																																												
Diameter (mm) 107																																																																												
Invert Level (m) 62.774																																																																												
Minimum Outlet Pipe Diameter (mm) 150																																																																												
Suggested Manhole Diameter (mm) 1200																																																																												
<table><tr><td>Control Points</td><td>Head (m)</td><td>Flow (l/s)</td><td>Control Points</td><td>Head (m)</td><td>Flow (l/s)</td></tr><tr><td>Design Point (Calculated)</td><td>2.119</td><td>7.0</td><td>Kick-Flo®</td><td>0.957</td><td>4.8</td></tr><tr><td>Flush-Flo™</td><td>0.469</td><td>6.1</td><td>Mean Flow over Head Range</td><td>-</td><td>5.6</td></tr></table>					Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)	Design Point (Calculated)	2.119	7.0	Kick-Flo®	0.957	4.8	Flush-Flo™	0.469	6.1	Mean Flow over Head Range	-	5.6																																																						
Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)																																																																							
Design Point (Calculated)	2.119	7.0	Kick-Flo®	0.957	4.8																																																																							
Flush-Flo™	0.469	6.1	Mean Flow over Head Range	-	5.6																																																																							
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated																																																																												
<table><tr><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td></tr><tr><td>0.100</td><td>3.7</td><td>1.200</td><td>5.4</td><td>3.000</td><td>8.2</td><td>7.000</td><td>12.3</td></tr><tr><td>0.200</td><td>5.4</td><td>1.400</td><td>5.8</td><td>3.500</td><td>8.9</td><td>7.500</td><td>12.7</td></tr><tr><td>0.300</td><td>5.9</td><td>1.600</td><td>6.1</td><td>4.000</td><td>9.4</td><td>8.000</td><td>13.1</td></tr><tr><td>0.400</td><td>6.0</td><td>1.800</td><td>6.5</td><td>4.500</td><td>10.0</td><td>8.500</td><td>13.5</td></tr><tr><td>0.500</td><td>6.1</td><td>2.000</td><td>6.8</td><td>5.000</td><td>10.5</td><td>9.000</td><td>13.9</td></tr><tr><td>0.600</td><td>6.0</td><td>2.200</td><td>7.1</td><td>5.500</td><td>11.0</td><td>9.500</td><td>14.3</td></tr><tr><td>0.800</td><td>5.6</td><td>2.400</td><td>7.4</td><td>6.000</td><td>11.4</td><td></td><td></td></tr><tr><td>1.000</td><td>4.9</td><td>2.600</td><td>7.7</td><td>6.500</td><td>11.9</td><td></td><td></td></tr></table>					Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	0.100	3.7	1.200	5.4	3.000	8.2	7.000	12.3	0.200	5.4	1.400	5.8	3.500	8.9	7.500	12.7	0.300	5.9	1.600	6.1	4.000	9.4	8.000	13.1	0.400	6.0	1.800	6.5	4.500	10.0	8.500	13.5	0.500	6.1	2.000	6.8	5.000	10.5	9.000	13.9	0.600	6.0	2.200	7.1	5.500	11.0	9.500	14.3	0.800	5.6	2.400	7.4	6.000	11.4			1.000	4.9	2.600	7.7	6.500	11.9		
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)																																																																					
0.100	3.7	1.200	5.4	3.000	8.2	7.000	12.3																																																																					
0.200	5.4	1.400	5.8	3.500	8.9	7.500	12.7																																																																					
0.300	5.9	1.600	6.1	4.000	9.4	8.000	13.1																																																																					
0.400	6.0	1.800	6.5	4.500	10.0	8.500	13.5																																																																					
0.500	6.1	2.000	6.8	5.000	10.5	9.000	13.9																																																																					
0.600	6.0	2.200	7.1	5.500	11.0	9.500	14.3																																																																					
0.800	5.6	2.400	7.4	6.000	11.4																																																																							
1.000	4.9	2.600	7.7	6.500	11.9																																																																							
Hydro-Brake® Optimum Manhole: 10 HB, DS/PN: 2.002, Volume (m³): 13.2																																																																												
Unit Reference MD-SHE-0107-6000-1575-6000																																																																												
Design Head (m) 1.575																																																																												
Design Flow (l/s) 6.0																																																																												
Flush-Flo™ Calculated																																																																												
Objective Minimise upstream storage																																																																												
Application Surface																																																																												
Sump Available Yes																																																																												
Diameter (mm) 106																																																																												
Invert Level (m) 62.249																																																																												
Minimum Outlet Pipe Diameter (mm) 150																																																																												
©1982-2020 Innovyze																																																																												


Coast Consulting Engineers Ltd				Page 4			
Suite 6, Vita House		FLOSH MEADOWS					
Fish Quay		CLEATOR					
North Shields NE30 1JA		1:100 +50%					
Date 09/06/2023		Designed by RH					
File 230609 REVISED SURFACE W...		Checked by PL					
Innovyze		Network 2020.1					
<hr/>							
Hydro-Brake® Optimum Manhole: 10 HB, DS/PN: 2.002, Volume (m³): 13.2							
Suggested Manhole Diameter (mm) 1200							
Control Points		Head (m)	Flow (l/s)	Control Points		Head (m)	Flow (l/s)
Design Point (Calculated)		1.575	6.0	Kick-Flo®		0.952	4.7
Flush-Flo™		0.468	5.9	Mean Flow over Head Range		-	5.2
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated							
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.6	1.200	5.3	3.000	8.1	7.000	12.1
0.200	5.3	1.400	5.7	3.500	8.7	7.500	12.5
0.300	5.7	1.600	6.0	4.000	9.3	8.000	12.9
0.400	5.9	1.800	6.4	4.500	9.8	8.500	13.3
0.500	5.9	2.000	6.7	5.000	10.3	9.000	13.7
0.600	5.9	2.200	7.0	5.500	10.8	9.500	14.0
0.800	5.5	2.400	7.3	6.000	11.3		
1.000	4.9	2.600	7.6	6.500	11.7		
<hr/>							
Hydro-Brake® Optimum Manhole: 17 HB, DS/PN: 1.009, Volume (m³): 9.6							
Unit Reference MD-SHE-0235-3200-1642-3200							
Design Head (m)				1.642			
Design Flow (l/s)				32.0			
Flush-Flo™				Calculated			
Objective				Minimise upstream storage			
Application				Surface			
Sump Available				Yes			
Diameter (mm)				235			
Invert Level (m)				61.852			
Minimum Outlet Pipe Diameter (mm)				300			
Suggested Manhole Diameter (mm)				1800			
Control Points		Head (m)	Flow (l/s)	Control Points		Head (m)	Flow (l/s)
Design Point (Calculated)		1.642	32.0	Kick-Flo®		1.101	26.4
Flush-Flo™		0.503	32.0	Mean Flow over Head Range		-	27.5
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated							
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	7.8	0.200	23.7	0.300	30.6	0.400	31.7
<hr/>							
©1982-2020 Innovyze							


Coast Consulting Engineers Ltd		Page 6																																																																								
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:100 +50%																																																																									
Date 09/06/2023	Designed by RH																																																																									
File 230609 REVISED SURFACE W...	Checked by PL																																																																									
Innovyze	Network 2020.1																																																																									
<div>Storage Structures for 180518 SW1.SWS</div> <div>Cellular Storage Manhole: 1, DS/PN: 1.000</div> <div>Invert Level (m) 63.585 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>51.8</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>51.8</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table> <div>Cellular Storage Manhole: 2, DS/PN: 1.001</div> <div>Invert Level (m) 63.015 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>220.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>220.0</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table> <div>Cellular Storage Manhole: 4, DS/PN: 1.003</div> <div>Invert Level (m) 62.589 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>129.5</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>129.5</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table> <div>Cellular Storage Manhole: 6, DS/PN: 1.005</div> <div>Invert Level (m) 62.335 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>25.9</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>25.9</td><td>0.0</td><td></td><td></td><td></td></tr></tbody></table>			Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	51.8	0.0	0.521	0.0	0.0	0.520	51.8	0.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	220.0	0.0	0.521	0.0	0.0	0.520	220.0	0.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	129.5	0.0	0.521	0.0	0.0	0.520	129.5	0.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	25.9	0.0	0.521	0.0	0.0	0.520	25.9	0.0			
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	51.8	0.0	0.521	0.0	0.0																																																																					
0.520	51.8	0.0																																																																								
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	220.0	0.0	0.521	0.0	0.0																																																																					
0.520	220.0	0.0																																																																								
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	129.5	0.0	0.521	0.0	0.0																																																																					
0.520	129.5	0.0																																																																								
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	25.9	0.0	0.521	0.0	0.0																																																																					
0.520	25.9	0.0																																																																								
©1982-2020 Innovyze																																																																										

Coast Consulting Engineers Ltd			Page 7																																																																										
Suite 6, Vita House		FLOSH MEADOWS																																																																											
Fish Quay		CLEATOR																																																																											
North Shields NE30 1JA		1:100 +50%																																																																											
Date 09/06/2023		Designed by RH																																																																											
File 230609 REVISED SURFACE W...		Checked by PL																																																																											
Innovyze			Network 2020.1																																																																										
<p><u>Cellular Storage Manhole: 7, DS/PN: 1.006</u></p> <p>Invert Level (m) 62.224 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>25.9</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>25.9</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p><u>Cellular Storage Manhole: 8, DS/PN: 2.000</u></p> <p>Invert Level (m) 63.413 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>77.7</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>77.7</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p><u>Cellular Storage Manhole: 9, DS/PN: 2.001</u></p> <p>Invert Level (m) 62.621 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>388.5</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>388.5</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p><u>Cellular Storage Manhole: 10 HB, DS/PN: 2.002</u></p> <p>Invert Level (m) 62.249 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>170.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>170.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p><u>Cellular Storage Manhole: 11, DS/PN: 2.003</u></p> <p>Invert Level (m) 62.181 Infiltration Coefficient Side (m/hr) 0.00000 Infiltration Coefficient Base (m/hr) 0.00000 Safety Factor 2.0</p>						Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	25.9	0.0	0.521	0.0	0.0	0.520	25.9	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	77.7	0.0	0.521	0.0	0.0	0.520	77.7	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	388.5	0.0	0.521	0.0	0.0	0.520	388.5	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	170.0	0.0	0.521	0.0	0.0	0.520	170.0	0.0			
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	25.9	0.0	0.521	0.0	0.0																																																																								
0.520	25.9	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	77.7	0.0	0.521	0.0	0.0																																																																								
0.520	77.7	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	388.5	0.0	0.521	0.0	0.0																																																																								
0.520	388.5	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	170.0	0.0	0.521	0.0	0.0																																																																								
0.520	170.0	0.0																																																																											
©1982-2020 Innovyze																																																																													

Coast Consulting Engineers Ltd			Page 8																																																																										
Suite 6, Vita House		FLOSH MEADOWS																																																																											
Fish Quay		CLEATOR																																																																											
North Shields NE30 1JA		1:100 +50%																																																																											
Date 09/06/2023		Designed by RH																																																																											
File 230609 REVISED SURFACE W...		Checked by PL																																																																											
Innovyze			Network 2020.1																																																																										
<p style="text-align: center;"><u>Cellular Storage Manhole: 11, DS/PN: 2.003</u></p> <p style="text-align: center;">Porosity 0.95</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>200.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>200.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 12, DS/PN: 2.004</u></p> <p style="text-align: center;">Invert Level (m) 62.079 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>129.5</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>129.5</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 15, DS/PN: 1.008</u></p> <p style="text-align: center;">Invert Level (m) 61.919 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>30.0</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>30.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 16, DS/PN: 3.000</u></p> <p style="text-align: center;">Invert Level (m) 61.900 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>51.8</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>51.8</td><td>0.0</td><td></td><td></td><td></td></tr></table> <p style="text-align: center;"><u>Cellular Storage Manhole: 17 HB, DS/PN: 1.009</u></p> <p style="text-align: center;">Invert Level (m) 61.852 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</p>						Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	200.0	0.0	0.521	0.0	0.0	0.520	200.0	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	129.5	0.0	0.521	0.0	0.0	0.520	129.5	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	30.0	0.0	0.521	0.0	0.0	0.520	30.0	0.0				Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	51.8	0.0	0.521	0.0	0.0	0.520	51.8	0.0			
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	200.0	0.0	0.521	0.0	0.0																																																																								
0.520	200.0	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	129.5	0.0	0.521	0.0	0.0																																																																								
0.520	129.5	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	30.0	0.0	0.521	0.0	0.0																																																																								
0.520	30.0	0.0																																																																											
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																																																																								
0.000	51.8	0.0	0.521	0.0	0.0																																																																								
0.520	51.8	0.0																																																																											
©1982-2020 Innovyze																																																																													


Coast Consulting Engineers Ltd			Page 9																				
Suite 6, Vita House		FLOSH MEADOWS																					
Fish Quay		CLEATOR																					
North Shields NE30 1JA		1:100 +50%																					
Date 09/06/2023		Designed by RH																					
File 230609 REVISED SURFACE W...		Checked by PL																					
Innovyze			Network 2020.1																				
<p style="text-align: center;"><u>Cellular Storage Manhole: 17 HB, DS/PN: 1.009</u></p> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>77.7</td><td>0.0</td><td>0.521</td><td>0.0</td><td>0.0</td></tr><tr><td>0.520</td><td>77.7</td><td>0.0</td><td></td><td></td><td></td></tr></table>						Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	0.000	77.7	0.0	0.521	0.0	0.0	0.520	77.7	0.0			
Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)																		
0.000	77.7	0.0	0.521	0.0	0.0																		
0.520	77.7	0.0																					
©1982-2020 Innovyze																							

Coast Consulting Engineers Ltd								Page 10																																																																																																																																																																																					
Suite 6, Vita House Fish Quay North Shields NE30 1JA				FLOSH MEADOWS CLEATOR 1:100 +50%																																																																																																																																																																																									
Date 09/06/2023				Designed by RH																																																																																																																																																																																									
File 230609 REVISED SURFACE W...				Checked by PL																																																																																																																																																																																									
Innovyze				Network 2020.1																																																																																																																																																																																									
<u>Summary of Critical Results by Maximum Level (Rank 1) for 180518 SW1.SWS</u>																																																																																																																																																																																													
<u>Simulation Criteria</u>																																																																																																																																																																																													
Areal Reduction Factor		1.000		Additional Flow - % of Total Flow		0.000																																																																																																																																																																																							
Hot Start (mins)		0		MADD Factor * 10m³/ha Storage		2.000																																																																																																																																																																																							
Hot Start Level (mm)		0		Inlet Coefficient		0.800																																																																																																																																																																																							
Manhole Headloss Coeff (Global)		0.500		Flow per Person per Day (l/per/day)		0.000																																																																																																																																																																																							
Foul Sewage per hectare (l/s)		0.000																																																																																																																																																																																											
Number of Input Hydrographs		0		Number of Storage Structures		13																																																																																																																																																																																							
Number of Online Controls		3		Number of Time/Area Diagrams		0																																																																																																																																																																																							
Number of Offline Controls		0		Number of Real Time Controls		0																																																																																																																																																																																							
<u>Synthetic Rainfall Details</u>																																																																																																																																																																																													
Rainfall Model		FSR		Ratio R		0.220																																																																																																																																																																																							
Region England and Wales Cv (Summer)		1.000																																																																																																																																																																																											
M5-60 (mm)		18.600		Cv (Winter)		1.000																																																																																																																																																																																							
Margin for Flood Risk Warning (mm)		300.0																																																																																																																																																																																											
Analysis Timestep		2.5		Second Increment (Extended)																																																																																																																																																																																									
DTS Status		OFF																																																																																																																																																																																											
DVD Status		OFF																																																																																																																																																																																											
Inertia Status		OFF																																																																																																																																																																																											
Profile(s)		Summer and Winter																																																																																																																																																																																											
Duration(s) (mins)		15, 30, 60, 120, 180, 240, 360																																																																																																																																																																																											
Return Period(s) (years)		100																																																																																																																																																																																											
Climate Change (%)		50																																																																																																																																																																																											
<table><tr><th></th><th>US/MH</th><th></th><th>Return</th><th>Climate</th><th>First (X)</th><th>First (Y)</th><th>First (Z)</th><th>Overflow</th><th>Water</th></tr><tr><th>PN</th><th>Name</th><th>Storm</th><th>Period</th><th>Change</th><th>Surcharge</th><th>Flood</th><th>Overflow</th><th>Act.</th><th>Level</th></tr><tr><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th>(m)</th></tr><tr><td>1.000</td><td>1</td><td>360 Winter</td><td>100</td><td>+50%</td><td>100/180 Summer</td><td></td><td></td><td></td><td>64.689</td></tr><tr><td>1.001</td><td>2</td><td>360 Winter</td><td>100</td><td>+50%</td><td>100/180 Summer</td><td></td><td></td><td></td><td>64.689</td></tr><tr><td>1.002</td><td>3 HB</td><td>360 Winter</td><td>100</td><td>+50%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>64.690</td></tr><tr><td>1.003</td><td>4</td><td>60 Summer</td><td>100</td><td>+50%</td><td>100/30 Summer</td><td></td><td></td><td></td><td>62.851</td></tr><tr><td>1.004</td><td>5</td><td>120 Summer</td><td>100</td><td>+50%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>62.788</td></tr><tr><td>1.005</td><td>6</td><td>180 Summer</td><td>100</td><td>+50%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>62.729</td></tr><tr><td>1.006</td><td>7</td><td>360 Summer</td><td>100</td><td>+50%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>62.700</td></tr><tr><td>2.000</td><td>8</td><td>360 Winter</td><td>100</td><td>+50%</td><td>100/180 Summer</td><td></td><td></td><td></td><td>63.794</td></tr><tr><td>2.001</td><td>9</td><td>360 Winter</td><td>100</td><td>+50%</td><td>100/60 Summer</td><td></td><td></td><td></td><td>63.794</td></tr><tr><td>2.002</td><td>10 HB</td><td>360 Winter</td><td>100</td><td>+50%</td><td>100/15 Summer</td><td></td><td></td><td></td><td>63.792</td></tr><tr><td>2.003</td><td>11</td><td>360 Summer</td><td>100</td><td>+50%</td><td>100/120 Summer</td><td></td><td></td><td></td><td>62.691</td></tr><tr><td>2.004</td><td>12</td><td>360 Summer</td><td>100</td><td>+50%</td><td>100/60 Summer</td><td></td><td></td><td></td><td>62.685</td></tr><tr><td>2.005</td><td>13</td><td>360 Summer</td><td>100</td><td>+50%</td><td>100/60 Summer</td><td></td><td></td><td></td><td>62.680</td></tr><tr><td>1.007</td><td>14</td><td>360 Summer</td><td>100</td><td>+50%</td><td>100/60 Summer</td><td></td><td></td><td></td><td>62.674</td></tr><tr><td>1.008</td><td>15</td><td>360 Summer</td><td>100</td><td>+50%</td><td>100/30 Summer</td><td></td><td></td><td></td><td>62.656</td></tr></table>											US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water	PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level										(m)	1.000	1	360 Winter	100	+50%	100/180 Summer				64.689	1.001	2	360 Winter	100	+50%	100/180 Summer				64.689	1.002	3 HB	360 Winter	100	+50%	100/15 Summer				64.690	1.003	4	60 Summer	100	+50%	100/30 Summer				62.851	1.004	5	120 Summer	100	+50%	100/15 Summer				62.788	1.005	6	180 Summer	100	+50%	100/15 Summer				62.729	1.006	7	360 Summer	100	+50%	100/15 Summer				62.700	2.000	8	360 Winter	100	+50%	100/180 Summer				63.794	2.001	9	360 Winter	100	+50%	100/60 Summer				63.794	2.002	10 HB	360 Winter	100	+50%	100/15 Summer				63.792	2.003	11	360 Summer	100	+50%	100/120 Summer				62.691	2.004	12	360 Summer	100	+50%	100/60 Summer				62.685	2.005	13	360 Summer	100	+50%	100/60 Summer				62.680	1.007	14	360 Summer	100	+50%	100/60 Summer				62.674	1.008	15	360 Summer	100	+50%	100/30 Summer				62.656
	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water																																																																																																																																																																																				
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level																																																																																																																																																																																				
									(m)																																																																																																																																																																																				
1.000	1	360 Winter	100	+50%	100/180 Summer				64.689																																																																																																																																																																																				
1.001	2	360 Winter	100	+50%	100/180 Summer				64.689																																																																																																																																																																																				
1.002	3 HB	360 Winter	100	+50%	100/15 Summer				64.690																																																																																																																																																																																				
1.003	4	60 Summer	100	+50%	100/30 Summer				62.851																																																																																																																																																																																				
1.004	5	120 Summer	100	+50%	100/15 Summer				62.788																																																																																																																																																																																				
1.005	6	180 Summer	100	+50%	100/15 Summer				62.729																																																																																																																																																																																				
1.006	7	360 Summer	100	+50%	100/15 Summer				62.700																																																																																																																																																																																				
2.000	8	360 Winter	100	+50%	100/180 Summer				63.794																																																																																																																																																																																				
2.001	9	360 Winter	100	+50%	100/60 Summer				63.794																																																																																																																																																																																				
2.002	10 HB	360 Winter	100	+50%	100/15 Summer				63.792																																																																																																																																																																																				
2.003	11	360 Summer	100	+50%	100/120 Summer				62.691																																																																																																																																																																																				
2.004	12	360 Summer	100	+50%	100/60 Summer				62.685																																																																																																																																																																																				
2.005	13	360 Summer	100	+50%	100/60 Summer				62.680																																																																																																																																																																																				
1.007	14	360 Summer	100	+50%	100/60 Summer				62.674																																																																																																																																																																																				
1.008	15	360 Summer	100	+50%	100/30 Summer				62.656																																																																																																																																																																																				
©1982-2020 Innovyze																																																																																																																																																																																													

Coast Consulting Engineers Ltd		Page 11
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:100 +50%	
Date 09/06/2023 File 230609 REVISED SURFACE W...	Designed by RH Checked by PL	
Innovyze	Network 2020.1	

Summary of Critical Results by Maximum Level (Rank 1) for 180518 SW1.SWS


PN	US/MH Name	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Half Drain	Pipe	Status	Level Exceeded
		Depth (m)	Volume (m³)			Time (mins)	Flow (l/s)		
1.000	1	0.701	0.000	0.01		99	7.6	SURCHARGED	
1.001	2	0.806	0.000	0.01			6.5	SURCHARGED	
1.002	3 HB	1.691	0.000	0.18			6.7	FLOOD RISK	
1.003	4	0.037	0.000	0.77		25	28.3	SURCHARGED	
1.004	5	0.124	0.000	1.00			35.6	SURCHARGED	
1.005	6	0.169	0.000	1.01		110	36.3	SURCHARGED	
1.006	7	0.252	0.000	0.91		149	31.3	SURCHARGED	
2.000	8	0.683	0.000	0.06		62	14.5	SURCHARGED	
2.001	9	0.904	0.000	0.09			21.5	SURCHARGED	
2.002	10 HB	1.168	0.000	0.06			5.9	FLOOD RISK	
2.003	11	0.136	0.000	0.15		160	15.3	SURCHARGED	
2.004	12	0.232	0.000	0.26		199	21.6	SURCHARGED	
2.005	13	0.268	0.000	0.26			21.7	SURCHARGED	
1.007	14	0.306	0.000	0.38			36.0	SURCHARGED	
1.008	15	0.362	0.000	0.39		254	36.2	SURCHARGED	

Coast Consulting Engineers Ltd		Page 12
Suite 6, Vita House Fish Quay North Shields NE30 1JA	FLOSH MEADOWS CLEATOR 1:100 +50%	
Date 09/06/2023	Designed by RH	
File 230609 REVISED SURFACE W...	Checked by PL	
Innovyze	Network 2020.1	


Summary of Critical Results by Maximum Level (Rank 1) for 180518 SW1.SWS

US/MH		Return Climate		First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act. Level
								(m)
3.000	16	360 Summer	100	+50%	100/30 Summer			62.640
1.009	17 HB	360 Summer	100	+50%	100/15 Summer			62.639
1.010	18	240 Summer	100	+50%				61.920

US/MH		Surcharged	Flooded	Flow / Overflow		Half Drain	Pipe	Level	
PN	Name	Depth (m)	Volume (m³)	Cap.	(l/s)	Time (mins)	Flow (l/s)	Status	Exceeded
3.000	16	0.365	0.000	0.16		254	13.9	SURCHARGED	
1.009	17 HB	0.487	0.000	0.50		273	32.0	SURCHARGED	
1.010	18	-0.123	0.000	0.66			32.0	OK	



- Highways**
1. All excavations below adopted highways to be backfilled with Type 1 and compacted in layers not exceeding 150mm.
 2. Highway Authority to be contacted as soon as Contractor is aware of any proposed works with the Clerk of Works.
 3. General Drainage
 4. All gullies to be trapped as shown on the details.
 5. All gullies to be trapped as shown on the details.
 6. All gullies to be trapped as shown on the details.
 7. All gullies to be trapped as shown on the details.
 8. All gullies to be trapped as shown on the details.
 9. All gullies to be trapped as shown on the details.
 10. All gullies to be trapped as shown on the details.
 11. All gullies to be trapped as shown on the details.
 12. All gullies to be trapped as shown on the details.
 13. All gullies to be trapped as shown on the details.
 14. All gullies to be trapped as shown on the details.
 15. All gullies to be trapped as shown on the details.
 16. All gullies to be trapped as shown on the details.
 17. All gullies to be trapped as shown on the details.
 18. All gullies to be trapped as shown on the details.
 19. All gullies to be trapped as shown on the details.
 20. All gullies to be trapped as shown on the details.
 21. All gullies to be trapped as shown on the details.
 22. All gullies to be trapped as shown on the details.
 23. All gullies to be trapped as shown on the details.
 24. All gullies to be trapped as shown on the details.
 25. All gullies to be trapped as shown on the details.
 26. All gullies to be trapped as shown on the details.
 27. All gullies to be trapped as shown on the details.
 28. All gullies to be trapped as shown on the details.
 29. All gullies to be trapped as shown on the details.
 30. All gullies to be trapped as shown on the details.
 31. All gullies to be trapped as shown on the details.
 32. All gullies to be trapped as shown on the details.
 33. All gullies to be trapped as shown on the details.
 34. All gullies to be trapped as shown on the details.
 35. All gullies to be trapped as shown on the details.
 36. All gullies to be trapped as shown on the details.
 37. All gullies to be trapped as shown on the details.
 38. All gullies to be trapped as shown on the details.
 39. All gullies to be trapped as shown on the details.
 40. All gullies to be trapped as shown on the details.
 41. All gullies to be trapped as shown on the details.
 42. All gullies to be trapped as shown on the details.
 43. All gullies to be trapped as shown on the details.
 44. All gullies to be trapped as shown on the details.
 45. All gullies to be trapped as shown on the details.
 46. All gullies to be trapped as shown on the details.
 47. All gullies to be trapped as shown on the details.



TYPICAL SECTION THROUGH SWALE AT NORTHERN BOUNDARY



Coast Consulting Engineers Ltd

7 Silverton Court

Northumberland Business Park

NE23 7RY

Tel. 0191 597 7879