

GARAGE CONSTRUCTION NOTES.

Roof

Trusses to be done to manufactures specification, breathable felt, laths, tiles as garage roof.

Walls

250 cavity work, s/a ties for every other course, every 900 horizontally staggered, openings and render as garage.

Floor

100 mm conc floated smooth, 1200g dpm turned up at the sides to top dpc.

Sand blinded hardcore on solid bottom.

Fl 100 mm above GL. Conc ramp to door

Foundations

Strip concrete, 600 wide x 150 thick on solid bottom

Proposed finishes

Roof Grey conc tiles.

Walls dry dash