NOTES

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. THE INFORMATION SHOWN ON THIS DRAWING IS INTENDED TO PROVIDE A GENERAL OUTLINE OF THE HIGHWAY WORKS. PLEASE REFER TO THE DETAILED DESIGN DRAWINGS FOR SPECIFIC SCHEME DETAILS.
3. PLEASE REFER TO STREET LIGHTING DESIGN PACKAGE FOR FURTHER DETAILS AND INFORMATION.
4. THIS DRAWING SHOULD BE READ IN RELATION TO THE SUBJECT OF THE TITLE ONLY. OTHER INFORMATION SHOWN ON THE DRAWING IS TO BE CONSIDERED INDICATIVE ONLY.
5. ALL DIMENSIONS ARE IN METRES UNLESS SPECIFIED OTHERWISE.
6. ALL LEVELS TO BE CHECKED BY THE CONTRACTOR AT THE START OF WORKS AND ANY DISCREPANCIES NOTIFIED TO THE ENGINEER.
7. WHERE NECESSARY THE RELEVANT SECTIONS OF THE DESIGN MANUAL FOR ROADS AND BRIDGES, SPECIFICATION AND BRITISH STANDARDS.
8. ALL MATERIALS TO BEAR THE RELEVANT B.S. KITEMARK AND COMPLY FULLY WITH THE SPECIFICATIONS. ALL CONCRETE & CONCRETE PRODUCTS MUST USE SULPHATE RESISTANT CEMENT (UNLESS THE SITE INVESTIGATION REPORT PROVES THAT SULPHATE ATTACK FROM SOILS AND GROUNDWATER WILL NOT OCCUR).
9. ALL STATUTORY CONSENTS, OPENING NOTICES ETC. AS REQUIRED UNDER HIGHWAYS ACTS AND WATER INDUSTRIES ACTS ARE TO BE OBTAINED BY THE CONTRACTOR PRIOR TO COMMENCEMENT OF THE WORKS (UNLESS OTHERWISE STATED).
10. PRESENCE OF STATUTORY UNDERTAKERS EQUIPMENT IN THE HIGHWAY SHOULD BE VERIFIED BY THE CONTRACTOR ON SITE PRIOR TO STARTING ANY WORKS. THE CONTRACTOR SHOULD CONFIRM THE LOCATION OF ALL STATS PLANT BY HAND DUG TRIAL TRENCHES PRIOR TO COMMENCING ANY WORKS. ALLOWANCE FOR THE PRESENCE OF ALL STATS APPROPRIATE PROTECTION / DIVERSION MEASURES IS TO BE PUT IN PLACE BY THE CONTRACTOR (UNLESS STATED OTHERWISE) WHERE STATS EQUIPMENT ARE FOUND TO BE WITHIN THE AREA OF HIGHWAY WORKS. NECESSARY DIVERSION/PROTECTION REQUIREMENTS TO BE AGREED WITH SERVICE PROVIDER.
11. ALL SETTING OUT TO BE AGREED PRIOR TO COMMENCEMENT OF CONSTRUCTION.
12. AREA OF RESURFACING AT TIE-IN TO EXISTING SURFACE TO BE AGREED ON SITE.
13. PLEASE REFER TO LANDSCAPE ARCHITECT DRAWINGS PACKAGE FOR FURTHER DETAILS AND INFORMATION.
14. PLEASE REFER TO MECHANICAL/ELECTRICAL DRAWINGS PACKAGE FOR FURTHER DETAILS AND INFORMATION ON ELECTRICAL CONNECTIONS/DISCONNECTIONS, DUCTING LAYOUTS FOR EV CHARGING POINT AND POWER SUPPLY, ETC.
15. PLEASE REFER TO BGP DRAWINGS PACKAGE FOR FURTHER DETAILS AND INFORMATION REGARDING THE DRAINAGE PROPOSALS.
16. NEW TEMPORARY SIGNS TO DIAGRAM 7014 (NEW ROAD LAYOUT AHEAD) TO BE PROVIDED ON ALL APPROACH ROADS. EXACT LOCATION TO BE AGREED WITH OVERSEEING ORGANISATION. SIGNS TO BE TAKEN DOWN BY CONTRACTOR AFTER 3 MONTHS OF THE COMPLETION OF THE WORKS

KEY - GENERAL ARRANGEMENT

- 1 — CARRIAGEWAY, REFER TO DRAWINGS LUF-TTE-ZZ-XX-D-H-0700 & 0701 FOR DETAILS
- 2 — FOOTWAY, REFER TO DRAWING LUF-TTE-ZZ-XX-D-H-1100 & 1101 FOR DETAILS
- 3 — SOFT LANDSCAPING, REFER TO ONE-ENVIRONMENT DRAWINGS FOR DETAILS
- 4 — PERMEABLE BLOCK PAVING, REFER TO DRAWING LUF-TTE-ZZ-XX-D-H-0700 & 0701 FOR DETAILS
- 5 — CONCRETE HARDSTANDING, REFER TO DRAWING LUF-TTE-ZZ-XX-D-H-1100 & 1101 FOR DETAILS
- TACTILE PAVING, REFER TO DRAWING LUF-TTE-ZZ-XX-D-H-1100 & 1101 FOR DETAILS
- CORDUROY PAVING, REFER TO DRAWING LUF-TTE-ZZ-XX-D-H-1100 & 1101 FOR DETAILS
- RED LINE BOUNDARY

IMPORTANT CDM / H&S NOTE

THE DESIGNERS WOULD DRAW THE READER'S ATTENTION TO KEY RESIDUAL CONSTRUCTION HEALTH AND SAFETY HAZARDS THAT HAVE NOT BEEN ELIMINATED FROM DESIGNS SHOWN ON THE DRAWINGS BY THE DESIGN PROCESS. THESE HAZARDS ARE IDENTIFIED BELOW:

HR REF	HAZARD
1	SERVICES KNOWN AND UNKNOWN
2	EXISTING SOFT GROUND CONDITION/COLLAPSE OF EXCAVATIONS AND UNSTABLE GROUND
3	CONTACT WITH MOVING PLANT
4	INTERFACE WITH PUBLIC HIGHWAY TRAFFIC
5	HEALTH HAZARDS
6	GAS GOVERNOR

ANY CONSTRUCTION PERSONNEL INCLUDING OPERATIVES INTENDING TO CONSTRUCT THE DESIGNS SHOWN ON THIS DRAWING SHOULD ENSURE THAT THEY HAVE BEEN THOROUGHLY BRIEFED BY THE PRINCIPAL CONTRACTOR ON ALL HEALTH AND SAFETY MATTERS AND HAVE SIGHT OF:
- THE FULL DESIGNERS AND CONTRACTORS HAZARD AND RISK ASSESSMENTS AND RISK REGISTERS.
- THE DEVELOPED CONSTRUCTION PHASE HEALTH AND SAFETY PLAN
- THE CONTRACTORS CONSTRUCTION METHOD STATEMENTS.

FOR APPROVAL

Rev	Description	Date	Drn	Chk	App
P01	STAGE 4 ISSUE	24.10.2025	LJB	MB	LB

Document Control

Issuing Office
Tetra Tech Manchester
2nd Floor,
11 York Street,
Manchester, M2 2AW
Tel: +44 (0)161 872 3223
www.tetratecheurope.com

TETRA TECH

Client
MORGAN SINDALL

Project Name
CMIQ PHASE 2 LUF - PLOT 12

Sheet Title
GENERAL ARRANGEMENT
SHEET 2 OF 2

TTE Project Number	Drawn By	Date	Checked By	Date	Approved By	Date	Scale @ A1	Suitability
784-B065555	LJB	Sep' 25	MB	Sep' 25	LB	Sep' 25	1:250	S0

Client Project Number	Originator	Volume/System	Level/Location	Type/Code	Role	Number	Revision
LUF	TTE	ZZ	XX	D	H	0101	P01

© Copyright Tetra Tech TTE_MT_v1