

Sunbelt Rentals Ltd.  
102 Dalton Ave  
Birchwood Park  
Risley  
Warrington  
WA3 6YE

20<sup>th</sup> April 2023

Delivery to HMP Haverigg

### **Quotation**

Dear Sarah,

Quotation for a 2-bay polytunnel measuring 16m wide x 24.4m in length consisting of two 8m wide bays with approx. 2.2m clearance under the gutter.

### **Specification:**

#### **Main Frame**

Tubular steel framework manufactured from 60mm diameter pre-galvanised steel tube. Hoops spaced 2.44m apart. Additional 50mm diameter bracing bars (crop bars) supplied for every hoop with 35mm 'V' hangers. Heavy duty telescopic foundation poles to allow hoop jacking for cover tensioning.



### Gutters

Internal 'valley' gutter mounted on independent 50mm diameter posts. Gutters manufactured from 2mm thick aluminium sheet. No outer (side) gutters required.

### End Frames & Doors

Timber end frames at both ends of both bays using 75mm x 75mm pressure treated timber. Ends to be clad with polythene and fixed using 50mm x 12mm timber laths. 2.6m wide double-leaf, sliding, aluminium doors fitted to both ends of one bay only.

### Cladding

Clad with 'light diffusing' polythene, 180mu thickness, 5-year guarantee (10 year life expectancy). Padded foam tape (anti-hot spot tape) to be applied to the top surface of all the steel hoops prior to the polythene covers being fitted.

### Sides

Two 100mm x 50mm side rails, one attached approx. 1.5m off the ground and one at ground level. Manual gearbox-operated, polypropylene, roll-up screens to be fitted on both sides of the structure operating between the base rail and the mid-rail. 40% shade netting attached to the outside between the two rails. Both side nets include a 30cm high, translucent-white, PVC-coated fabric skirt to prevent draughts when the screens are closed.

### Construction

Construction to take place on a flat, level site prepared by yourselves. **Price includes plant hire and concrete.**

Polytunnel Materials	£17,600.00
Polytunnel Construction	£8,900.00
Sub total	£26,500.00
VAT	£5,300.00
<b>Total</b>	<b>£31,800.00</b>

20% deposit with order  
50% on delivery  
30% on completion

Valid for 30 days.

Yours,

**Nigel Carr**

Commercial Director