



Meadow Mix Seeding		
Specification	Sowing Rate	Area / m2
EM2 Emorsgate or similair	4 g/m2	291
	Total	291

Trees			
Species	Specification	Density	Number
Acer campestre	30-35cm girth, 2m clear stem, root ball		3
		Total	3

Hedges				
Species	Specification	Density	Percentage	Number
Crataegus monogyna	120-150cm high well feathered, bare root	7/lin.m, double row	50%	176
Rosa canina	120-150cm high well feathered, bare root	7/lin.m, double row	10%	35
Acer campestre	120-150cm high well feathered, bare root	7/lin.m, double row	10%	35
Sambucus nigra	120-150cm high well feathered, bare root	7/lin.m, double row	10%	35
Ligustrum vulgare	120-150cm high well feathered, bare root	7/lin.m, double row	10%	35
Viburnum opulus	120-150cm high well feathered, bare root	7/lin.m, double row	10%	35
		Total		351

NOTES

- Native Hedge Mix
- Meadow Mix Seeding
- Proposed Tree
- Asphalt Concrete [Pedestrian Specification]
- Asphalt Concrete [Vehicular Specification]

REVISION | P02      DATE | 03.03.22      BY | KJ      CHECKED | PA

Updated planting plan

REVISION | P01      DATE | 02.03.22      BY | KJ      CHECKED | PA

First Issue

CLIENT      Copeland Borough Council

PROJECT      **Cleator Moor Innovation Quarter (BOC Yard)**

TITLE      Site - Proposed Landscape

DWG No.      N1045-ONE-ZZ-XX-DR-L-0201      REV      P02

STATUS      Preliminary

SCALE      1:200      @      A3      DATE      02.03.22      DRN BY      KJ



ONE-ENVIRONMENTS