

PLAN

RAMP ELEVATION

SHOP SIDE ELEVATION

LIGHTING & MATERIALS

ARROW NOTATION LEGEND

WALL LIGHT

LIGHTING

TIMBER SLEEPER RAISED PLANTER WITH SHRUBS

SOFT LANDSCAPING

SIGN 2.1

SIGNAGE



LIGHTING

O BOLLARD LIGHT Kit Clic Post 40 H1000 LU14805B Lombardo S 1000mm H x 147mm D x 92mm W (max dims)

Cabin Entrances: Clic Wall LU14802B Lombardo S 90mm H x 107mm D x 92mm W (max dims)

Cabin Entrances: Tape 140 LL14502B2 Lombardo S 90mm H x 140mm D x 23mm W (max dims)

Cabin Entrances:

Tape 140 LL14502B2

Lombardo S

Site Shop Cabin:

Ramp. Koi 220 LL1210242

Lombardo S

Lombardo S

Entrance. Wall mounted. Trend Flat 200 LL1120232

110mm H x 220mm D x 32mm W (max dims)

40mm H x 112mm D x 190mm W (max dims)

90mm H x 140mm D x 23mm W (max dims)









PLANTING SCHEDULE \downarrow

WILDFLOWER PLANTING:

All open areas that are in heavy shade will be planted with a mixture to establish wildflowers in areas of heavy or dense shade. Species in this mix are frequently found in wooded areas, alongside woodland edges and where shade may be heavy or prolonged.

These areas will be planted with:

Agrimony, Angelica, Avens, Bedstraw, Bellflower, Betony, Bluebell, Buttercup, Campion, Clary, Columbine, Foxglove, Hedge Parsley, Meadowsweet, Mustard, Ragged Robin, Sage, St John's-wort, Teasel, Vetch, Vetch, Wild Garlic / Ramsons, Woundwort, Yarrow.

All open areas not in shade will be planted with traditional wildflowers that are easily established and contains species frequently found in a diverse range of soil types and habitats.

These areas will be planted with:

Bedstraw, Black Medick, Burnet, Buttercup, Campion, Campion, Carrot, Catchfly, Clary, Cowslip, Daisy, Forget-me-not, Foxglove, Goat's-beard, Knapweed Common, Knapweed Greater, Musk Mallow, Self-heal, Sorrel, St John's-wort, Yarrow, Yellow Rattle.

HEDGEROWS:

All existing hedgerows will be rejuvenated, where hedgerow is missing or damaged/dead we will be replacing with a mixture of the following:

Hawthorn, Blackthorn, Field Maple, Alder, Wild Privet, Wild Cherry, Bird Cherry, Guelder Rose, Spindle, Juneberry.

Hedgerow boarders internal and external will be planted with UK native Cornfield Annuals wildflower containing: Corn Chamomile, Corn Cockle, Cornflower, Marigold Corn, Common Poppy.

The 850 new hedgerow that has already been planted is a mixed native RSPB approved bird friendly hedging specifically chosen for their value to birds, insects and other small animals, and consists of Hawthorn, Blackthorn, Guelder Rose, Alder and Field Maple. In addition to these I am due to receive another 150 hedgerow plants this week which will be used to fill any remaining gaps in the existing hedgerows. (All can be evidenced with receipts should they be required. All of the above are from the RHS "Perfect For Pollinators" list and are beneficial in creating a long lasting meadow and wildlife habitat.

WOODLAND:

Where trees are no longer safe and where trees have historically been felled, we will be replanting with: 3-7 years old and consist of saplings consisting of 22 in total planted randomly as per plan, these consist of: 1 apple, 4 sweet chestnut, 3 horse chestnut, 4 walnut, 2 oak, 1 ash, 1 hazelnut, 1 field maple, 4 Scot pines and 1 wild cherry these will be planted between the cabins to maintain woodland.

MAINTENANCE OF PLANTING \downarrow


PLANTING ESTABLISHMENT MAINTENANCE. INITIAL PLANTING.

- All planting of saplings will initially be staked and tied with expandable tie straps.
- saplings to be protected by 'spiral tube' tree guards. • inspected weekly to check support and protection remains intact, change out any broken or damaged elements.
- ensure ground is hydrated, water where ground observed to be dry.
- remove any excess grass / weed growth from within tube.

ESTABLISHMENT PERIOD (up to 6 months)

- inspect fortnightly to check support and protection remains intact, change out any broken or damaged elements. • ensure ground is hydrated, water where ground observed to be dry. inspect more frequently in dry periods.
- remove any excess grass / weed growth from within tube.
- replace any saplings that are in poor health or have died away.

- MID TERM (after 6 months)
- inspect at least every 4 weeks to check support and protection remains intact, change out any broken or damaged elements.
- ensure ground is hydrated, water where ground observed to be dry. inspect more frequently in dry periods. • remove any excess grass / weed growth from within tube.
- replace any saplings that are in poor health or have died away.
- LONG TERMS (after 18 months)



• continue weekly inspections to detect any damage to saplings.



LANDSCAPING





LIMITATIONS OF USE.

NOTES:

- 1. These drawings are only to be used for the 'drawing type' stated and as such are not suitable for any other use. The drawings should **not** be scaled from for obtaining detailed
- dimensional information unless the dimension is stated on the drawings 3. Discrepancies should be reported to HDP Ltd immediately.
- 4. Drawings and designs should not be reproduced unless strict agreement is sort from HDP Ltd.
- The drawings and design are the property of HDP Ltd. 6. The drawings are for the sole use of the client. A third party using
- these drawings does so at their own risk. Unless stated otherwise any boundary lines shown are based on
- Ordanance Survey mapping and on site check dimensions. They should not be relied upon for correct boundary demarcation.

Copyright © All Rights Reserved of Holdsworth Design Practice Ltd All drawings & designs are the copyright of Holdsworth Design Practice Ltd. They should not in any event be copied, reproduced or duplicated without the prior approval of Holdsworth Design Practice Ltd.

REV No. REVISIONS REV 0 FIRST ISSUE 1.09.24 ADDED DETAIL TO PLANTING SCHEDULE TEXT REV 1 AND ALTERED PLAN NOTATION TO HIGHLIGHT 27 11 24 LANDSCAPED AREAS REV 2 UPDATED LIGHTING PRODUCTS AND INFORMATION 15.12.24



3 The Woodlands, Hayton, CA8 9HZ M: 07769700912 E: andrew@hdpttd.co.uk W: www.hdpttd.co.uk

PROPOSED LIGHTING & LANDSCAPING

Project Motor home and log cabin site with shop.

Client Mr & Mrs Usher. Partfield Park, Drigg.

DRAWING TYPE. PLANNING CONDITIONS (PC)	DRWG No. USH.CS.1222. PL.LDSCP1
DATE 15.12.24	REV 2
SCALE A1 1:200	