

REV	DATE	DESCRIPTION	DRW	CHK
P01	09/08/2021	PRELIMINARY ISSUE	GS	MP
P02	12/04/2024	REVISED TO UU COMMENTS	SNK	GS
P03	28/04/2024	REVISED TO UU COMMENTS	SNK	GS
P04	25/07/2024	REVISED TO UU COMMENTS	SNK	GS
C01	07/11/2024	TENDER ISSUE	SNK	GS
C02	12/02/2025	REVISED TO UU COMMENTS	SNK	GS
C03	17/03/2025	REVISED TO UU COMMENTS	MH	SNK
C04	24/04/2025	REVISED TO UU COMMENTS	SNK	MP
C05	01/05/2025	REVISED TO UU COMMENTS	SNK	MP
C06	06/05/2025	REVISED TO UU COMMENTS	SNK	MP

HEALTH & SAFETY

1. CONTRACTOR SHOULD BE AWARE OF GENERAL CONSTRUCTION RISKS TO PREVENT SLIPS, TRIPS AND FALLS AND TAKE NECESSARY PRECAUTIONS WITHOUT SPECIAL INSTRUCTION.

2. CONTRACTOR TO PROVIDE TRENCH SUPPORTS AS APPROPRIATE AND ENSURE THAT PLANT REMAINS A SAFE DISTANCE FROM TRENCHES PRIOR TO INSTALLING DRAINAGE.

3. THE TIME THAT EXCAVATIONS ARE OPEN ON SITE SHOULD BE KEPT TO A MINIMUM AND ALL TRENCHES SHOULD BE SURROUNDED BY A BARRIER.

4. CONNECTIONS TO EXISTING SEWERS TO BE MADE BY NVL APPROVED CONTRACTOR ONLY.

5. CONTRACTOR TO MAKE OPERATIVES AWARE OF ASSOCIATED DANGERS TO HEALTH SUCH AS LEPTOSPIROSIS (WELLS DISEASE) AND RECOMMENDED PRECAUTIONS. ADEQUATE WELFARE FACILITIES AND PROTECTIVE CLOTHING TO BE PROVIDED AS REQUIRED.

6. UNFINISHED MANHOLES MUST BE COVERED WITH LOAD BEARING MATERIALS AND SURROUNDED WITH BARRIER.

PIPES & CABLES

7. SERVICE RECORDS TO BE REFERRED TO PRIOR TO WORK COMMENCING. CONTRACTOR TO PROCEED WITH CAUTION AND SERVICES TO BE LOCATED BY HAND DIG AND PROTECTED ACCORDINGLY.

8. CONTRACTOR TO ENSURE RELEVANT MEASURES ARE TAKEN TO KEEP PLANT AND PEOPLE A SAFE DISTANCE FROM STEEP SLOPES DURING THE WORKS.

9. CONTRACTOR TO ENSURE THAT PROCEDURES ARE IN PLACE TO KEEP PEOPLE A SAFE DISTANCE FROM WORKING PLANT WHERE NECESSARY.

10. CONTRACTOR TO REFER TO GROUND INVESTIGATION REPORT FOR CONTAMINATION TESTS AND TO PROVIDE ADEQUATE WELFARE FACILITIES AND PROTECTIVE CLOTHING AS REQUIRED.

KEY

Retaining wall (retained height shown)
(edge protection required over 500mm ht)

Flag On Edge. Maximum retained height 0.4m. Not to be constructed supporting driveways or highways

Steps - 250mm Going 150mm Rise
(Handrails required to heights over 600mm)

Proposed Finished Floor Level

Proposed spot height

Existing spot height

Proposed Gradient

Proposed Engineered Batter / Embankment
(1:2.5 Grad Max unless notes otherwise)

RW 0.6M
FOE 0.4M
FFL 141.000
+141.00
+141.00
1:12
W W W W

FULL CCTV OF 375mm TO BE ABANDONED NOT POSSIBLE, PIPEWORK TO BE EXPOSED AND INSPECTED BY UNITED UTILITIES INSPECTOR PRIOR TO ANY ABANDONMENT WORKS

ABANDONMENTS MUST BE WITNESSED BY A UU INSPECTOR FOR THE STATUS OF THE PIPE TO BE CHANGED ON THE PUBLIC SEWER RECORDS, MINIMUM OF 72 HOURS' NOTICE WILL BE PROVIDED

SUBJECT TO THE APPROVAL OF ALL RELEVANT AUTHORITIES

Client
Aldi Stores Ltd.

Project Title
Aldi - Whitehaven

Project Address
Preston Street Whitehaven

Drawing Title
Proposed Sewer Diversion

Job No.	Originator	Zone	Level	Type	Role
79-EXXX 3E	ZZ	XX	DR	C	
System Classification	Drawing No.	Suitability	Revision		
Ro 50_20_11 -6000	D2	C06			
Drawn	Checked	Date	Scale	Size	
GS	-	Aug 2021	1:250	A1	

Newcastle Office
2 Esh Plaza, Sir Bobby Robson Way
Great Park, Newcastle upon Tyne
NE13 9BA

Wakefield Office
4 Calder Close, Calder Park
Wakefield
WF4 3BA

London Office
WolWork Moorgate, 1 Fore Street Ave,
London
EC2Y 9DT

Consulting Engineers
www.3econult.com
tel: 0191 230 2993
newcastle@3econult.com

