FOR CONSTRUCTION

Rev:	Date:	Comments:	By:
F	5/6/26	Up-dated external with further details	MD
E	20/05/26	Up-dated external paving and gate added to office access pathway	MD
D	20/04/26	Up-dated external paving proposals	MD
B	12/02/26	Up-dated external paving proposals	MD
A	5/12/25	Up-dated proposals	MD

Client:

Cumberland Council
Millom Arts and Enterprise Hub

DAY CUMMINS LIMITED

Architects & Surveyors
Lakeland Business Park
Cockermouth Cumbria CA13 0QT
Tel: 01900 820700
Fax: 01900 820701
email: dc@day-cummins.co.uk
www.day-cummins.co.uk

Project:
Extension and Refurbishment of the Former Bank, 5 St George's Road Millom LA18 4JA

Drawing Title:
Proposed Site Plan

Drawn:	Checked:	Signed:
MD	JM	
Scale: 1:100	Date: 5/6/2024	Paper Size: A2

ALL DIMENSIONS TO BE CHECKED ON SITE
FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS
THIS DRAWING IS COPYRIGHT

Project No:	Drawing No:	Rev:
6027	27	F

Standard tree Height 4.5 - 5m

Ornamental Tree Height 2.5 -3m

Specimen shrub size 15 - 20L

ORNAMENTAL MIX PLANTING
Mix of shrubs, groundcover and pollination freindly shade tolerant herbaceous perennials

EDIBLE HERB MIX PLANTING
Edible herbs planted into gravel substrate eg rosemary

WOODLAND MIX PLANTING
Mix of evergreen shrubs, groundcover and edible woodland plant species

PERENNIAL PLANTING
Mix of textured grasses and structural perennial species

Habtat box - Swift nest box x3
By Nestbox uk. On North elevation near the eaves (min 5m above GFL)
see ecologist survey report

Habitat Box - Nesting box x3
For smaller species to North or East elevation (2- 4m above GFL) By Nestbox uk. See ecologist survey report

Coloured precast paving textured paving 600 x 600 x 40mm colour Charcoal and Natural from Tobermore with 50mm flat top kerb to boarders

Soft landscape areas for planting

Gravel finish adjacent to building perimeter and to rear of the extension

See Planting schedule in the design access statement for soft planting details

Existing trees to be remove see tree survey

0 1 2 3 4 5

Existing stone wall boundary to be repaired

Existing neighbours trees to be retained and protected - see tree report

Existing trees shown dotted to be removed. Refer to tree survey.

new close boarded timber nfill to extg gate and former window openings

North