



GENERAL

1. All dimensions are in metres unless noted otherwise
2. DO NOT SCALE THIS DRAWING - If in doubt ask
3. All dimensions & levels to be checked by the Contractor prior to commencement of work, any discrepancy shall be reported immediately to the Engineer.
4. Underground services are present in the area. Contractor is to confirm the precise line and depth of any services prior to the commencement of any excavation works.
5. All work shall be carried out in accordance with Local Authority, Statutory Authority, Health & Safety requirements and regulations.
6. The drawings shall be read in accordance with all other contract documents relevant at that time of issue and during the period of the contract.
7. The Contractor must ensure the overall stability of the works is adequate at all stages of the construction.
8. All chamber covers, valve boxes etc., situated within the works to be raised/lowered to match proposed levels where necessary.
9. All setting out shall be agreed on site with the overseeing organisation.
10. All works are to be in accordance with the Cumberland Council design guide for Highways & Transport and the Specification for Highway Works.
11. All works & legal boundaries to be applied to topographical survey. OS Mapping for illustrative purposes only.

Key
--- Existing kerb to be removed
Existing inspection chamber / manhole to be raised / lowered to proposed levels
Existing fire hydrant / SV to be raised / lowered to suit proposed levels
Existing Gully to be retained
Existing pole to be removed
Existing street lighting column to be relocated
Existing bollard to be removed
Existing ACO drain to be removed and relocated to back of proposed footway

Client	ALDI
Drawing	S278 Works - Site Clearance
Drawn By	RID
Checkd	GDM
Drawing No	AMA-48019-D-200
Date	07.01.2026
Scale	1:200
Sheet	A1
Revision	C01